

UBC Social Ecological Economic Development Studies (SEEDS) Sustainability Program

Student Research Report

Redesign of Chancellor Boulevard / Wesbrook Mall Intersection at UBC

Jeffrey Chun

Nathan Chan

Jessica Francis

Nishchhal Gautam

Ryan Li

Jason Wen

University of British Columbia

CIVL 445 - Engineering Design and Analysis II

April 7, 2017

Disclaimer: "UBC SEEDS Sustainability Program provides students with the opportunity to share the findings of their studies, as well as their opinions, conclusions and recommendations with the UBC community. The reader should bear in mind that this is a student research project/report and is not an official document of UBC. Furthermore, readers should bear in mind that these reports may not reflect the current status of activities at UBC. We urge you to contact the research persons mentioned in a report or the SEEDS Sustainability Program representative about the current status of the subject matter of a project/report".

CIVL 446 Final Report

**REDESIGN OF CHANCELLOR BOULEVARD /
WESBROOK MALL INTERSECTION AT UBC**



Submitted to:

Krista Falkner, P.Eng.

Transportation Engineer

UBC Campus and Community Planning

Client: University of British Columbia – UBC SEEDS (Social Ecological Economic Development) Sustainability Program

TEAM 16

Jeffrey Chun

Nathan Chan

Jessica Francis

Nishchhal Gautam

Ryan Li

Zicheng (Jason) Wen

April 7, 2017

April 7th, 2017

Department of Civil Engineering
Faculty of Applied Science
2002 - 6250 Applied Science Lane
Vancouver, BC Canada V6T 1Z4

Campus + Community Planning
2210 West Mall
Vancouver, BC Canada V6T 1Z4

Dear Ms. Krista Falkner,

Thank you for the opportunity to submit a design proposal to the University of British Columbia, for the Chancellor Boulevard and Wesbrook Mall Intersection design. At your request, the following tasks have been completed to design the intersection:

- Completing a study to identify the intersection design most suited to the site
- Modeling current and projected traffic with multiple designs
- Selecting an intersection design and completing preliminary drawings
- Producing a cost estimate
- Producing a construction schedule
- Providing a presentation of the proposed deliverables

Enclosed is our proposal which will provide you with our design, cost and a construction schedule for construction management services.

If you have any questions or would like any clarifications, please contact our project team. We look forward to working with you again in the future.

Regards,

Team 16 Consulting

Team 16 Consulting

Encl. Redesign of Chancellor boulevard and Wesbrook Mall Intersection at UBC

EXECUTIVE SUMMARY

The existing intersection at Chancellor Boulevard and Wesbrook Mall on the University of British Columbia Vancouver Campus (UBC) currently serves as the northern entry point into campus. The existing site does not support heavy vehicles or provide a welcoming entrance to UBC. Additionally, the intersection does not provide safe access for crossing pedestrians. The upgrade of Chancellor Boulevard and Wesbrook Mall was established as a project to address these issues.

The proposed upgrade will include a single lane roundabout with crosswalks at all approaches. Additionally, electrical conduits will be installed at each crosswalk for future upgrades to include pedestrian-controlled beacons. Furthermore, bike lanes will be provided along Chancellor Boulevard, as well as the removal of the existing merge-and-turn lanes along Chancellor Boulevard to create additional green-space. The roundabout centre itself will be 18 meters in diameter to accommodate heavy vehicle turning.

The center of the roundabout has a proposed gateway structure. The structure is a multi-purpose structure to serve both as a small exhibition center, viewing platform as well as a gateway entrance into campus. Entrance to the center will be provided via a staircase constructed along the westbound direction of Chancellor Boulevard, and an exposed elevated concrete walkway which will extend towards the main structure located in the roundabout. Additionally, a gateway sign of the University of British Columbia will be installed along the structure facing eastward to serve as an entrance into the campus.

In order to complete the construction of the roundabout with minimal impact to neighboring homes and the community, a phased construction schedule is proposed. Starting in May 2017 and completing in August 2017, the construction and traffic management plans allow for either two-way or one-way traffic along Chancellor Boulevard during all but one weekend of construction. Additionally, the gateway structure will be constructed at the beginning of the summer in 2018.

The cost of the project construction is estimated at \$1,733,800. This includes \$254,730 for the design of the project and \$1,479,000 for the construction. Additionally, construction management fees have been included as this is the preferred project delivery method.

Table of Contents

EXECUTIVE SUMMARY	ii
LIST OF ILLUSTRATIONS	v
DESIGN STANDARDS AND SOFTWARE PACKAGES	vii
1. INTRODUCTION	1
2. KEY PROJECT ISSUES AND CRITERIA	2
2.1. Project Overview	2
2.2. Technical Issues	3
2.3. Key Economic and Construction Issues	3
2.4. Regulatory Criteria	3
City of Vancouver.....	4
The University of British Columbia.....	4
Ministry of Transportation.....	4
Federal	4
Musqueam	4
2.5. Environmental Issues	5
Stormwater Management.....	5
2.6. Social Criteria	5
Stakeholders	6
3. ROUNDABOUT DESIGN	7
3.1. Key Design Features	7
3.2. Geometric Design	9
3.3. Traffic Analysis	10
Existing Traffic Analysis	10
Future Traffic Analysis.....	11
3.4. Geometric Inputs and Considerations	12
3.5. Traffic Operations	12
3.6. Construction Materials	12
Aggregates and Backfill	13
Concrete.....	14
Landscaping Materials	15
3.7. Site Investigation	15
4. Gateway Design	16
4.1. Structural Concept	16
4.2. Structural Design and Analysis	18
4.3. Foundation Design	18
4.4. Detailed Gateway Design	19
5. CONSTRUCTION METHODOLOGY	20
5.1. Construction Safety	20
5.2. Schedule	21
5.3. Traffic Management Plan	22
Stage 1 – Mobilization.....	22
Stage 2 – South West Island Demolition	23
Stage 3 – South East Island Demolition.....	24
Stage 4 – North East Median Construction	25
Stage 5 – North West Median Construction	26
Stage 6 – Northern Roundabout Construction	27

Stage 7 – Southern Roundabout Construction	28
Stage 8 – Electrical Trenching	29
Stage 9 - Roundabout Construction	30
Stage 10 – Paving and Painting	31
Stage 11 – Gateway Installation.....	32
6. COST ESTIMATION	33
6.1. Permitting	33
6.2. Consulting Project-Management.....	34
6.3. General Contractor	35
6.4. Subcontractors	35
Excavation	35
Utilities	35
Formwork and Concrete	36
Asphalt & Material Testing	36
Landscaping	36
Painting	36
Signage	36
Flagging	36
6.5. Gateway.....	37
6.6. Contingency.....	37
Works Cited.....	38
Appendix A – Conceptual Design Alternatives	39
Appendix B – Presentation Slides	43
Appendix C – Stakeholder Register	59
Appendix D – Drawing Package	61
Civil Drawing.....	62
Structural Drawing.....	64
Mechanical Drawing	68
Electrical Drawing	70
Appendix E – Traffic Analysis Results (Synchro)	72
Appendix F – Traffic Analysis Results (SimTraffic)	81
Delays – Morning (AM) 2016.....	82
Queues – Morning (AM) 2016	83
Delays – Afternoon (PM) 2016	84
Queues – Afternoon (PM) 2016.....	85
Delays – Morning (AM) 2040.....	86
Queues – Morning (AM) 2040	87
Delays – Afternoon (PM) 2040	88
Queues – Afternoon (PM) 2040.....	89
Appendix G – Sample Roundabout Calculation	90
Appendix H – Sample Gateway Calculations	92
Appendix I –Construction Schedule: Phase 1 - Roundabout	101
Appendix J –Construction Schedule: Phase 2 - Gateway.....	108
Appendix K –Traffic Management Plan Checklist	112
Appendix L –Cost Estimate	120
Appendix M –Presentation Poster	132

LIST OF ILLUSTRATIONS

List of Figures

Figure 1 - Overview of Proposed Roundabout Design	7
Figure 2 - Overview of Proposed Roundabout.....	9
Figure 3 - Gateway Design	16
Figure 4 - Gateway Design	17
Figure 5 - Stage 1: Mobilization & Site Plan	22
Figure 6 - Stage 2: Southwest Island Demolition.....	23
Figure 7 - Stage 3: Southeast Island Demolition.....	24
Figure 8 - Stage 3: Temporary Bus Accommodation	24
Figure 9 - Stage 4: East Median Demolition	25
Figure 10 – Stage 5: West Median Demolition and Northwest Island Construction	26
Figure 11 - Stage 6: Northern Roundabout Construction	27
Figure 12 - Stage 7: Southern Roundabout Construction	28
Figure 13 - Stage 8: Electrical Trenching	29
Figure 14 - Stage 9: Roundabout Construction	30
Figure 15 - Stage 10: Paving, Painting and Landscaping.....	31
Figure 16 - Stage 11: Gateway Installation	32
Figure 17 - Signalized Intersection: AutoCAD Layover.....	40
Figure 18 - Proposed Upgrades to Existing Intersection: AutoCAD Layover.....	41
Figure 19 - Criteria Weight for Decision Process	42
Figure 20 - Weighted Scores for Decision Making Process.....	42
Figure 21 - Legend for Delays per Vehicle	82
Figure 22 - Delays: 2016 AM Existing Intersection	82
Figure 23 - Delays: 2016 AM Proposed Roundabout.....	82
Figure 24 - Legend for Queues	83
Figure 25 - Queues: 2016 AM Existing Intersection.....	83
Figure 26 - Queues: 2016 AM Proposed Roundabout	83
Figure 27 - Delays: 2016 PM Existing Intersection	84
Figure 28 - Delays: 2016 PM Proposed Roundabout.....	84
Figure 29 - Queues: 2016 PM Existing Intersection	85
Figure 30 - Queues: 2016 PM Proposed Roundabout.....	85
Figure 31 - Delays: 2040 AM Existing Intersection	86
Figure 32 - Delays: 2040 AM Proposed Roundabout.....	86
Figure 33 - Queues: 2040 AM Existing Intersection.....	87
Figure 34 - Queues: 2040 AM Proposed Roundabout	87
Figure 35 - Delays: 2040 PM Existing Intersection	88
Figure 36 - Delays: 2040 PM Proposed Roundabout.....	88
Figure 37 - Queues: 2040 PM Existing Intersection	89
Figure 38 - Queues: 2040 PM Proposed Roundabout.....	89
Figure 39 - Intersection Sight Distance.....	91

List of Tables

<i>Table 1 - Team Contribution Breakdown.....</i>	<i>1</i>
<i>Table 2 - Level of Service for Traffic Conditions.....</i>	<i>10</i>
<i>Table 3 - Overview of SimTraffic Results: 2016 Morning (AM) Conditions.....</i>	<i>10</i>
<i>Table 4 - Overview of SimTraffic Results: 2016 Afternoon (PM) Conditions.....</i>	<i>11</i>
<i>Table 5 - Overview of SimTraffic Results: 2040 Morning (AM) Conditions.....</i>	<i>11</i>
<i>Table 6 - Overview of SimTraffic Results: 2040 Afternoon (PM) Conditions.....</i>	<i>11</i>
<i>Table 7 - Road Base Grading Limits.....</i>	<i>13</i>
<i>Table 8 - Sub-Base Grading Limits.....</i>	<i>13</i>
<i>Table 9 - Trench Backfill Grading Limits.....</i>	<i>14</i>
<i>Table 10 - Pipe Bedding Grading Limits.....</i>	<i>14</i>
<i>Table 11 - Key Structural Design Parameters.....</i>	<i>17</i>
<i>Table 12 - Structural Load Combinations.....</i>	<i>18</i>
<i>Table 14 - Structural Bill of Materials.....</i>	<i>19</i>
<i>Table 15 - Summary of Cost Estimate.....</i>	<i>33</i>
<i>Table 16 - Summary of Gateway Cost.....</i>	<i>37</i>

DESIGN STANDARDS AND SOFTWARE PACKAGES

Software	Version	Use
Civil3D	2016	Geometric Design and Construction Drawings
Vehicle Tracking	2016	Traffic Analysis
Synchro	6	Traffic Analysis
SimTraffic	6	Traffic Analysis
SketchUp	2016	Graphics
Revit	2017	Graphics
SAP2000	19	Structural Analysis

Design Standard	Version	Use
HCM	2010	Highway Capacity Manual - Level of Service Designations
TAC	2007	Geometric Design Layouts and Site Distances
Worksafe BC	2016	Construction Phasing and Coordination
NBCC	2010	Structural Design Standard
ASTM	2008	Geotechnical Design Standard
MMCD	2010	Standard Details

1. INTRODUCTION

The existing intersection at Chancellor Boulevard and Wesbrook Mall serves as the northern entry point into the University of British Columbia (UBC). This stop and yield-controlled intersection will fail to meet future demands and currently does not support heavy vehicles. To address these issues, a roundabout replacement was proposed. This upgrade will include a single lane roundabout with crosswalks at all approaches and new bicycle lanes along Chancellor Boulevard. Furthermore, the removal of existing turning lanes and the addition of the roundabout, 18 meters in diameter, will create further green-space. The roundabout will feature a 6-meter high observation deck showcasing UBC's rich history and serve as an inviting gateway into the campus.

To minimize disturbance to neighboring homes and community, phased construction will commence May 2017 and be completed in August 2017. The proposed traffic management plan will allow for either two-way or one-way traffic along Chancellor Boulevard during all but one weekend of construction. Additionally, the gateway structure will be constructed at the beginning of the summer in 2018. The final cost of the project is estimated at \$1,733,800.

Table 1 - Team Contribution Breakdown

Team Contribution Breakdown		
Team Member	Role	Responsibility
Jeffrey Chun	<i>Structural Engineer</i>	<i>Regulatory Criteria, Social Criteria, Structural Considerations, Gateway Design, Construction Schedule</i>
Nathan Chan	<i>Structural Engineer</i>	<i>Key Project Criteria, Alternative Designs, Structural Considerations, Gateway Design, Construction Schedule</i>
Jessica Francis	<i>Project Manager</i>	<i>Title Page, Transmittal, Introduction, Construction Schedule, Traffic Management Plan, Formatting, Editing, Recorder, Appendices</i>
Nishchhal Gautam	<i>Geotechnical Engineer</i>	<i>Construction Materials, Geotechnical Considerations, Construction Schedule, 3D Modeller</i>
Ryan Li	<i>Traffic Engineer</i>	<i>Environmental Issues, Geometric Design, Synchro Analysis, Construction Schedule, Traffic Management Plan, AutoCAD, Utilities, Editing</i>
Jason Wen	<i>Estimator, Scheduler</i>	<i>Construction Schedule, MS Project, Cost Estimation</i>

2. KEY PROJECT ISSUES AND CRITERIA

The existing intersection configuration is becoming outdated in meeting growing demands, as it is unable to safely support pedestrian, cyclist, and vehicular traffic. The key issues of the intersection at Chancellor Boulevard are:

- Pedestrian safety, as the current intersection is not constructed with appropriate pedestrian and cyclist markings which is a major concern for public safety due to the lack of proper signage for the right of way
- The lack of accommodation for vehicular traffic as the existing configuration is unconventional which has caused confusion and a demand for more clear signage or road design.
- The growing demands of public transit from and towards the university, as the design capacity of the existing intersection will be exceeded in the near future

With the university's continued development and expansion, the intersection at Chancellor Boulevard serves as the main northern entrance into the campus and is a part of the university's plans for growth and improvement.

Some of the key issues found through site inspections and research is the lack of accommodation for non-vehicular traffic, such as lack of bicycle exclusive lanes, pedestrian crosswalk features, and a paved sidewalk for pedestrians to cross, risking the safety of public. A major concern is the unconventional intersection layout that has caused confusion and demand for more clear signage or road design. The intersection currently does not cater to the safety of pedestrian users, which will be addressed and focused as a fundamental part of the intersection.

2.1. Project Overview

Improvements to the existing intersection will be necessary as it does not address the safety of the road users and cannot meet the projected future traffic demand of 2% traffic growth per year. The existing design is unconventional in the Metro Vancouver region and less efficient compared to other campus entry points, such as the roundabout in the southern entrance. The main focus of the project is to address the following:

- Safety of road users (Campus and Community Planning, 2014)
- Stormwater Management and Landscaping Improvement (UBC Sustainability, 2014)
- Provision of an attractive visual gateway into campus
- Ensure stakeholder issues are accommodated

2.2. *Technical Issues*

For the redesign of the Chancellor Boulevard and Wesbrook Mall intersection, there were various site-specific constraints that were observed during site visits and initial feasibility studies. These constraints are outlined below:

- Existing utilities and storm water drainage must be diverted during construction and relocated to allow for excavation of the project solution
- The design will accommodate for large buses leaving the UBC bus loop and semi-trucks (WB-17)
- Drainage monitoring should be conducted on a weekly basis or after large rainfall events to ensure drainage from the site is not harmful to the environment
- Traffic management plans during all stages of construction will minimize disturbance to daily traffic

2.3. *Key Economic and Construction Issues*

Some of the key economic and construction issues are listed below:

- Limited space for storage – equipment and material, as well as deliveries will need to be coordinated and organized in advance
- Traffic control – the intersection is to be kept operational for as long as possible
- Timeframe – the construction should have minimal impact on the winter I and winter II semester traffic at UBC
- Property Lines – the project is constructed between The University Neighbourhood Association – Chancellor Place, the University Endowment Lands, and the Ministry of Transportation and Infrastructure
- Funding – as this is a Ministry of Transportation road a funding scheme is to be determined

2.4. *Regulatory Criteria*

For the design of the Chancellor Boulevard and Wesbrook Mall intersection, there are many governing bodies which the design must adhere to.

City of Vancouver

For projects constructed in the City of Vancouver, there are 5 sets of construction standards which must be followed (*The City of Vancouver , 2016*).

The Master Municipal Construction Document (MMCD) and the City's supplementary Street Restoration Manual provides specific measurements, drawings, and procedures for installing municipal infrastructure such as roundabouts. The TAC Geometric Design Guide will be used as the basis for the roundabout design as it provides recommended measurements and layouts for designing intersections. The Accessible Street Design Guide provides guidelines for street and sidewalk pedestrian accessibility to be used during the design phase of the intersection. The Street Tree Manual describes landscaping and tree planting concerns, which will be used during the restoration of the intersection after the main construction phase.

The University of British Columbia

The University of British Columbia has various guidelines and protocol for construction projects in the campus area outlined in Policy 92: Land Use and Permitting (*Campus and Community Planning, 2016*). The policy encompasses UBC's Land Use, Neighbourhood, and Vancouver Campus development plans and their associated permits. The permits and approval needed for the project will be obtained prior to the construction start date.

Ministry of Transportation

Traffic control for the redesign of Chancellor Boulevard and Wesbrook Mall intersection will follow traffic control protocol as outlined in the BC Ministry of Transportation's Traffic Control Manual for Work on Roadways (*Ministry of Transportation and Infrastructure, 2015*). In addition, construction practices for redesigning the intersection will adhere to Worksafe BC standards (*WorkSafeBC, 2016*).

Federal

Currently there is no need for federal involvement in the project.

Musqueam

As this project is not on Musqueam land, there are not regulatory concerns. However, the Musqueam people will be engaged as part of the stakeholder process.

2.5. *Environmental Issues*

The current layout of the stop-controlled intersection of Chancellor Boulevard and Wesbrook Mall consists largely of impermeable surfaces, thus there is room for improvement in regards to stormwater management. In addition, in the event of rainfall, stormwater can potentially transport grease and oil from the bus loop towards Chancellor Boulevard and Wesbrook Mall – which lead to fish habitat downstream. Due to the inherent function of a stop-controlled intersection, there is a significant amount of idling from vehicles due to the requirement of stopping – even in low-traffic scenarios. As a result, reduction of CO₂ and improvement to air quality is one of the reasons of the recommendation of a roundabout. It should be noted the project is relatively small in scale and does not require an environmental impact assessment.

Stormwater Management

The implementation of a roundabout will provide a generous amount of greenspace – within the roundabout, approach islands, and boulevards – relative to the existing layout of Chancellor Boulevard and Wesbrook Mall. During the construction of the roundabout, there is an opportunity to improve stormwater management by allowing water to infiltrate, while simultaneously providing additional stormwater drains.

2.6. *Social Criteria*

The social engagement activities provides a means for various project stakeholder groups to contribute and engage in the development of the design. It is an iterative process that identifies the concerns and issues from different stakeholder groups to be addressed into the final design and construction planning. The intersection project will consider and incorporate the feedback and advice from various social engagement activities where appropriate.

Stakeholders

A stakeholder register can be found in *Appendix C – Stakeholder Register* which outlines key project stakeholders, their involvement, and interest levels. A public consultation will take place before the detailed design is completed to engage stakeholders. As aforementioned, the project aims to align with UBC's initiatives, such as UBC's Transportation Plan 2040 and UBC's Sustainability initiative thus, close liaison with various UBC stakeholders will be conducted during the planning and construction phases of the project. The stakeholder register is very flexible and subject to change throughout the project as well as the stakeholder management classifications. Within the register, stakeholders are grouped into management categories:

Daily Communications

Stakeholders categorized with a (D) are expected to contribute to daily communication throughout the project. Generally these are full time workers on project. Company email address' will be used as well as company telephones. Many communications need to written and at all meeting minutes shall be enforced. These will be uploaded onto a shared project directory to be approved by two members of the meeting within 24 business hours of the meeting.

Weekly Communications

Stakeholders categorized with a (W) have the same expectations as daily communications except on a weekly basis.

Monthly Meetings

Stakeholders categorized with a (M) are invited and some are expected to attending monthly project meetings. These are for updates on the project and general overview with a large invested audience. Meeting minutes are also expected to be taken, reviewed, and then posted on the shared project drive.

Informal Communications

Stakeholders categorized with a (I) are expected to have informally scheduled project updates. This may include only access to the project data base, public consultations, or constant meetings but only at a particular phase of the project. A representative from stakeholder groups (I) maybe be invited to monthly meetings depending on the agenda.

3. ROUNDABOUT DESIGN

The following section will discuss the roundabout preliminary design and rationale.

3.1. Key Design Features

The preferred design for the Chancellor Boulevard and Wesbrook Mall intersection will be to implement a roundabout similar to the other vehicular entrances into the campus, which will address the key issues of pedestrian safety and increase in future traffic demands. The implementation of a roundabout is recommended to best satisfy safety and sustainability issues, as well as provide room for the addition of visual features to form a gateway into the UBC campus. Other designs were considered and can be found in *Appendix A – Conceptual Design Alternatives*.



Figure 1 - Overview of Proposed Roundabout Design

1. Intersection Safety

- Additional safety features for both pedestrians and cyclists by implementing crosswalks and a boulevard which isolates vehicular traffic
- Electrical connections will facilitate the upgrade of LED lighting for pedestrian crosswalks at all approaches
- The east approach cyclist lane will be integrated into the roundabout to provide cyclists a choice of cycling routes; to merge with vehicular traffic or dismount to avoid vehicular traffic
- Due to the nature of a roundabout design, vehicle speeds are generally slower, minimizing chance of collision and reducing severity of collisions

- Roundabouts are inherently safer as the type of collision is forced to sideswipe collisions, which is significantly less fatal compared to head-on or side collision found in the traditional intersection
- There is a concrete apron within the roundabout that allows for heavy vehicles – such as WB-17 and Articulated busses – to overtrack safely.
- The concrete apron also provides access for landscaping crews to maintain the greenspace near the roundabout; including the roundabout itself

2. Project Sustainability

- Additional green space at the roundabout and along the northern corridor improves stormwater management and landscaping features
- The roundabout design provides a more natural gateway into UBC, and allows for more opportunities for implementation of green space and landscaping around the site.

3. Traffic Capacity

- The AM Peak scenario was chosen as the baseline to perform the analyses due to the largest amount of volume amongst the three peaks (AM, Mid-day, and PM)
- Under 2016 traffic volumes, the roundabout performs well with an average delay per vehicle of less than 5 seconds; the remaining scenarios operate with an average delay per vehicle of approximately 10 seconds
- Under 2040 projected traffic volumes, the roundabout performs significantly better than the other scenarios, for further details refer to *Appendix E – Traffic Analysis Results (Synchro)*
- Vehicle Tracking results in AutoCAD show that an articulated bus can operate within the roundabout

4. Economic Performance

- As the roundabout serves as one of the main entrances into the university campus, the increase in traffic capacity can reduce future costs and collateral effects such as increasing the traffic demand of other entrances.
- Improvements to the existing stormwater management system – include additional drains along the west leg, and south leg – as part of the project will save costs in the future.

3.3. Traffic Analysis

Traffic analysis results are based on the 2010 Highway Capacity Manual (HCM) Level of Service (LOS) tables for unsignalized intersections. The corresponding delays – in seconds – will be provided for each approach. In addition, the 95th percentile queue length for each approach will also be identified. Further details will be provided in the form of graphics for existing and future scenarios, and can be found in *Appendix E – Traffic Analysis Results (Synchro)* and *Appendix F – Traffic Analysis Results (SimTraffic)*.

Table 2 - Level of Service for Traffic Conditions

2010 HCM LOS Table	
LOS	Delay (s)
A	<10
B	10-15
C	15-25
D	25-35
E	35-50
F	>50

Existing Traffic Analysis

In the 2016 existing traffic operations, there are projected improvements at all approaches through the implementation of the proposed roundabout. In addition, the 95th percentile queue lengths are also projected to improve along the east and south approach, for both the AM Peak. Similar improvements are also expected in the PM Peak; however, all approaches are anticipated to have shortened 95th queue lengths.

Table 3 - Overview of SimTraffic Results: 2016 Morning (AM) Conditions

<i>Intersection Configuration</i>	<i>Approach</i>	<i>Delays (s)</i>	<i>Level of Service</i>	<i>95th Percentile Queue (m)</i>
Existing	East	5-10	A	45
	South	5-10	A	25
	West	5-10	A	23
Roundabout	East	<5	A	42
	South	<5	A	21
	West	<5	A	28

Table 4 - Overview of SimTraffic Results: 2016 Afternoon (PM) Conditions

Intersection Configuration	Approach	Delays (s)	Level of Service	95 th Percentile Queue (m)
Existing	East	5-10	A	28
	South	5-10	A	25
	West	5-10	A	35
Roundabout	East	<5	A	17
	South	<5	A	19
	West	<5	A	24

Future Traffic Analysis

Under the projected 2040 traffic, significant delays along the east approach can be seen under the existing configuration of a stop-controlled intersection. With the implementation of the proposed roundabout, the east approach is anticipated to reduce delays and improve to a LOS A from LOS F, in the AM Peak. In the PM Peak, the west approach is expected to operate at LOS C under the existing stop-controlled configuration. However, the implementation of the proposed roundabout is anticipated to improve the west approach to operate at LOS A.

Table 5 - Overview of SimTraffic Results: 2040 Morning (AM) Conditions

Intersection Configuration	Approach	Delays (s)	Level of Service	95 th Percentile Queue (m)
Existing	East	40-60	F	96
	South	5-10	A	32
	West	5-10	A	23
Roundabout	East	5-10	A	55
	South	<5	A	25
	West	5-10	A	40

Table 6 - Overview of SimTraffic Results: 2040 Afternoon (PM) Conditions

Intersection Configuration	Approach	Delays (s)	Level of Service	95 th Percentile Queue (m)
Existing	East	5-10	A	30
	South	5-10	A	25
	West	15-25	C	90
Roundabout	East	<5	A	35
	South	5-10	A	40
	West	5-10	A	55

3.4. Geometric Inputs and Considerations

The proposed roundabout adheres to the standards found within the *BC Supplement to TAC Geometric Design Guide (Nyland, 2007)*. The articulated bus was selected as the design vehicle due to the Wesbrook Mall and Chancellor Boulevard junction serving as the collector route. AutoTURN/Vehicle Tracking was utilized to ensure the design vehicle is able to accommodate ingress to and egress traffic from UBC. As per the *BC Supplement to TAC Geometric Design Guide (Nyland, 2007)*, a minimum width of 1.8 m is to be provided at all sidewalks; the proposed roundabout upgrade provides a 2m sidewalk. Detectable warning surfaces are included at all sidewalk let-downs as additional means of providing warning of approaching vehicles. Calculations in regards to stopping sight distance and intersection sight distance can be seen in *Appendix G – Sample Roundabout Calculation*.

3.5. Traffic Operations

The proposed roundabout was analyzed under current traffic volumes and the anticipated 2040 volumes. The Highway Capacity Manual (HCM) 2010 standards for unsignalized operation was utilized for analysis (*Nyland, 2007*). Synchro was calibrated to model the current and anticipated future conditions; as a result, under the 2016 traffic volumes, all approaches operated with a level of service (LOS) A; this corresponds to a delay of less than 5 seconds. Under the anticipated 2040 traffic volumes, the west and south approach is expected to increase in delays with a LOS B; the east approach remains as LOS A.

3.6. Construction Materials

Following excavation of the site to a suitable depth, all backfill materials will be placed in uniform lifts not exceeding 200 mm loose thickness. All backfill materials shall also be compacted to a specified 95% of Modified Proctor Maximum Dry Density (ASTM D1557) (*Engineering Services, 2008*). Should the following specification be met, recycled asphalt product may be used.

Aggregates and Backfill

Road Base

150 mm of 19 mm Road Mulch of uniform quality, will be used up to the bottom of the asphalt. This material must adhere to the grading limits as shown below:

Table 7 - Road Base Grading Limits

SIEVE SIZE		% PASSING (by wt.)
19 mm	(3/4 in)	100
12.5 mm	(1/2 in)	61 - 95
9.5 mm	(3/8 in)	45 - 85
4.75 mm	(No. 4)	35 - 60
2.36 mm	(No. 8)	26 - 47
1.18 mm	(No. 16)	20 - 39
600 um	(No. 30)	13 - 29
300 um	(No. 50)	8 - 21
150 um	(No. 100)	5 - 15
75 um	(No. 200)	2 - 8

Sub-Base

450 mm of 75 mm crushed aggregates shall be placed between the sub-grade and the base course aggregates. This layer provides the strength and drainage to the pavement structure above. This material must meet the grading limits below:

Table 8 - Sub-Base Grading Limits

SIEVE SIZE		% PASSING (by wt.)
75 mm	(3 in)	100
19 mm	(3/4 in)	40 - 50
4.75 mm	(No. 4)	20 - 35
0.075 mm	(No. 200)	2 - 8

Sub-Grade Fill

The 75 mm crushed aggregate mentioned above may be used as sub-grade fill wherever needed. Native materials may also be used as sub-grade fill provided it is reviewed and approved by the City Engineer to save import costs.

Trench Backfill

Any trench fill to a maximum limit of 0.6 m below the base of pavement shall be done with a clean Sand fill. Clean sand contains trace to no organic matter and is of uniform quality. The grading limits should follow as shown below:

Table 9 - Trench Backfill Grading Limits

SIEVE SIZE		% PASSING (by wt.)
12.5 mm	(½ in)	100
9.5 mm	(3/8 in)	91 - 100
4.75 mm	(No. 4)	83 - 100
2.36 mm	(No. 8)	73 - 94
1.18 mm	(No. 16)	57 - 80
600 µm	(No. 30)	33 - 60
300 µm	(No. 50)	10 - 37
150 µm	(No. 100)	4 - 17
75 µm	(No. 200)	0 - 5

Pipe Bedding

20 mm crushed granular material of uniform quality and 100% mechanically crushed fragments with two or more fractured faces will be used as pipe bedding. The grading limits are shown below:

Table 10 - Pipe Bedding Grading Limits

SIEVE SIZE		% PASSING (by wt.)
19 mm	(¾ in)	100
12.5 mm	(½ in)	28 - 46
9.5 mm	(3/8 in)	8 - 21
4.75 mm	(No. 4)	3 - 11
2.36 mm	(No. 8)	0 - 6
1.18 mm	(No. 16)	0 - 2

Concrete

Concrete to be used for the footings shall be of 32 MPa and for sidewalks and curbs, 25 MPa may be used with adequate air content and slump. Concrete used for footings and sidewalks must have air content between 4% to 7% with slump of 80±20 mm. Concrete used for curbs may have slumps as low as 30 mm as it needs to be extruded from a curbing machine. All concrete poured on site should be tested for slump and air at intervals of 50 m³ to ensure specifications are being met. Concrete should be placed within 2 hours of batch time. Concrete using crushed recycled concrete as aggregates may be utilized if all other specifications are met.

Finished curb and gutter should have a smooth surface and free of voids or other irregularities. Sidewalks should be marked off in segments approximately 2.0 meters in length. If needed, control joints to minimize cracking may be installed as requested by the city. Furthermore, all sidewalk panels shall have a rough finish to aid with traction in wet conditions.

Landscaping Materials

Tree Placement is done with respect to the Street Tree Guidelines set forth by the City of Vancouver (*The City of Vancouver, 2016*). Trees will be spaced in order to maximize tree coverage while still respecting site lines, utilities and street lighting. Any new trees planted after construction should also match existing trees and spacing of the block. Average tree spacing will be approximately 8-10 meters based on existing trees along the block.

3.7. Site Investigation

Prior to construction and geotechnical investigations, utility locates will be conducted. These tests should be done by an independent third party to confirm the location and depths of existing utilities and pipes under the site, and to avoid any potential conflicts.

On February 1 2017, 4 hand auger tests were dug to a depth of approximately 1.0m. These test holes were backfilled immediately upon completion of soil logging. The purpose of these holes was to confirm stripping depths of asphalt and road base material for preparation of the roundabout for costing purposes.

Following these test holes, 2 Cone penetration tests (CPT) was also carried out to confirm the geologic layering of the site. These holes were drilled using a truck mounted drill rig. Both holes were drilled to an approximate depth of 7 meters below existing grade. All test holes were sealed as per provincial requirements upon completion.

4. Gateway Design

The purpose of the gateway structure is to provide a large scale structure to provide a visual entrance for the northern approach into the campus. The structure will also serve as an observation and deck for leisure purposes, allowing visitors and tourists to see the campus from the deck. A showcase of UBC's rich history is also proposed through the 580ft² elevated showcase room. The structure will symbolize the campus' natural environment, abundant history and the modern sustainability objectives of the institution.




Figure 3 - Gateway Design

4.1. Structural Concept

The structure is composed of two main sections; the wooden platform structure and an open steel walkway respectively. Timber is used as the main design material where plausible to provide a sustainable and aesthetic structure. A steel staircase and walkway serve as an entrance into the wooden platform structure, and provide an open walkway for visitors.



Figure 4 - Gateway Design

The gateway is designed as a light frame structure composed of a combination of steel and timber. The structure serves as an observation platform and gathering place for leisure in the summertime, therefore designed for larger live loads (assembly loading). The main structural issues, including likely failure mechanisms are listed below:

Table 11 - Key Structural Design Parameters

<i>Key Structural Design Issues/ Potential Failure Mechanisms</i>	<i>Description</i>
<i>Exposed Structure</i>	<i>Need to address issue of exposed structural elements</i>
<i>Earthquake Resistance</i>	<i>Lateral stability and unpredictable failure mechanism</i>
<i>Walkway over road</i>	<i>Long span causing deflection issues, need to ensure clearance requirements for vehicles</i>
<i>Accidental/Impact Loading</i>	<i>Structure is exposed, key structural components exposed to hazards</i>
<i>Large Gravity Loads</i>	<i>Large live loads need to be accounted for (assembly area loading)</i>

4.2. Structural Design and Analysis

The structure was analyzed using SAP 2000 and designed in accordance with the Wood Design Manual 2010 and the Handbook of Steel Construction 2010 respectively. Detailed calculations and analysis of critical members and connections, as well as design loads as per NBCC 2010, are shown in *Appendix H – Sample Gateway Calculations*.

The governing gravity and lateral load combinations as per NBCC 2010 are summarized below:

Table 12 - Structural Load Combinations

Gravity	Loading Combination: 3	1.25DL + 1.5LL (+0.5SL)	DL = Dead Load LL = Live Load SL = Snow Load E = Earthquake Load (Elastic Analysis)
Lateral	Loading Combination: 5	1.0DL + 1.0E	

4.3. Foundation Design

Square pad footings were selected to minimize excavation and costs while still suiting the structure's required loads. Additionally, to keep the design sustainable, the volume of concrete was minimized. A detail of one of the footings can be seen in *Appendix D – Drawing Package*.

The soil at the site of interest was taken as a Medium Sand with Friction angle (ϕ) and Unit weight (γ) of 30° and 18 kN/m³, respectively.

The allowable load on the soil was calculate using Terzaghi's bearing capacity theory. The table below summarizes the calculations. A factor of safety of 2.0 was used, where $FS = Q_{ult}/Q_{allowable}$.

$$Q_{ult} = \gamma' DN_q + 0.4\gamma' BN_\gamma$$

Where N_q and N_γ are Terzaghi's bearing capacity factors. Using a square footing of width, 1 meter, the allowable capacity ($Q_{allowable}$) was found to be 130 kPa. This ensures that 1 meter footings will suffice for a column loads up to 130 kN. All footings are placed 450 mm below ground to ensure frost protection.

4.4. Detailed Gateway Design

The critical members that were designed in the structure were the beams supporting the walkway, the columns supporting the walkway and staircase, the lateral bracing connection and the Cross-Laminated Timber decking on the wooden platform structure. A detailed summary of the structural members are shown in *Appendix D – Drawing Package*.

Table 13 - Structural Bill of Materials

Bill of Materials - Structural	
Steel	Qty.
W360x134	2
W360x33	6
HSS89x89x6.4	10
L76x76x7.9	12
A236 M22 Bolts	48
Timber	Qty.
5-PLY CLT, Stress Grade E2	1
D.Fir-L 24f EX 215x190	6
Timber Roof Truss	1

5. CONSTRUCTION METHODOLOGY

5.1. Construction Safety

The selected contractor will adhere WorkSafeBC's occupational health and safety (OHS) regulations, policies, and guidelines. The contractor is expected to prepare a project-specific safety management plan submitted to and approved by the owner, UBC Campus and Community Planning. During field inspections, should the contractor appear to be in violation of any articles from WorkSafeBC's OHS regulations, the field reviewer has authority to call for an inspection from WorkSafeBC at his/her discretion.

In this project, the prime consultant will require the following safety submissions from the contractor for review:

1. Shop drawings of trenching/shoring used for excavation, to be signed by independent reviewer specialized in trench/shore design. This can be done by contractor's in-house engineering, provided that it is submitted for review. Electrical and utilities trenching/tie-ins will not proceed without engineering sign-off.
2. Fall protection plan, produced by contractor's in-house and/or subcontracted engineering. To be approved by the owner's engineer(s). Gateway installation can be constructed up to ground level columns without owner's approval. Erection of the observation deck, walkway, and stairs cannot proceed without owner's approval.
3. Engineered rigging and lifts for critical lifts, to be signed off by a crane engineer. Rigging of heavy/wide gateway components (CLT deck slab, walkway girders) will be investigated by the crane subcontractor to determine if it is a critical lift. Erection of the observation deck and walkway cannot proceed without engineering sign-off.

The contractor shall be prepared to produce documentation of safety practices they have followed at any time, at the request of the owner and/or the prime consultant. These practices are not limited to activities listed above for submission and approval. The contractor and owner will also establish weekly safety shares and maintain a log of safety share minutes. When needed, the prime consultant, at the request of the owner and/or contractor, can attend safety shares to resolve site hazards.

5.2. Schedule

A preliminary construction schedule has been provided in *Appendix I –Construction Schedule*. Each stage of construction is discussed below with corresponding preliminary traffic management plan. Construction has been proposed in ten stages to keep traffic open for as long as possible. Generally construction work is scheduled for Monday to Friday, 7:00am – 3:00pm. When construction is not active, the existing intersection will be re-created with cones to keep traffic flowing. Once stage 9 is reached and the road is reopened the intersection will then operate as a roundabout. The below description and graphics of each construction phase will give an overview of construction activities and traffic diversions. At the end of each stage steel plate will cover trenches or gravel will be compacted for traffic to drive on. For length of activities please refer to the construction schedule provided in *Appendix I –Construction Schedule*. To determine the level of detail and risk for the traffic management plan the Ministry of Transportation checklist was completed and can be found in *Appendix K –Traffic Management Plan Checklist*.

5.3. Traffic Management Plan

The traffic management plan was developed in accordance to BC Ministry of Transportation and Infrastructure criteria as well as WorksafeBC. The stages outline below are for the construction of the roundabout only.

Stage 1 – Mobilization



Figure 5 - Stage 1: Mobilization & Site Plan

The fenced area shown above is a locked compound where the general contractor may store items. The proposed site layout has two parking spots, one for the superintendent and the other for visitors such as inspectors who will only be present for a small amount of time. All other workers are expected to park at the Rose Garden or North Parkade. The Northern acceleration lane will be utilized for deliveries during this stage.

Stage 2 – South West Island Demolition



Figure 6 - Stage 2: Southwest Island Demolition

In order for more space to be obtained the southeast island was selected as the first stage of demolition. The right turn lane from the west approach will be closed off to provide space for the demolition and allow a truck for removal/delivery; however the intersection will function normally with the addition of two flaggers to ensure the safety of all workers and the general public. Once the island is removed it will be replaced with gravel and then compacted for vehicle to drive over in the future. Cones will be put in place to re-create the island and keep the intersection geometry the same as before construction.

Stage 3 – South East Island Demolition



Figure 7 - Stage 3: Southeast Island Demolition

Similar to the stage previous the southeast island will be removed next using the traffic plan as above.



Figure 8 - Stage 3: Temporary Bus Accommodation

In preparation for upcoming traffic diversions part of the median will need to be removed at the adjacent intersection eastward, Chancellor Boulevard and Western Parkway. During upcoming construction there will be one-way traffic on Chancellor Boulevard that will at times utilize either the eastbound or westbound lane; in order for articulated buses to make this lane change, the median must temporarily be cut back and compacted to be operated as road space.

Stage 4 – North East Median Construction



Figure 9 - Stage 4: East Median Demolition

In order to accommodate the roundabout the east approach to the intersection must be moved slightly south so through traffic does not continue in a straight trajectory. The east island must also be shortened to accommodate the center of the roundabout. In order for this construction to take place the east approach of Chancellor Boulevard must be closed from Western Parkway to Wesbrook Mall. Traffic will be one way on and diverted to the west approach. There will be flaggers present during the day and cones will be set up to re-create the existing intersection at night. Trenching will also begin to move the existing storm drain to the new curb as well as electrical for the future addition of pedestrian lights and roundabout lighting.

Stage 5 – North West Median Construction



Figure 10 – Stage 5: West Median Demolition and Northwest Island Construction

Similar to the previous stage, the east approach of Chancellor Boulevard will be closed. In this stage the closure will start at Wesbrook Mall until Theology Mall. The closure is to accommodate the construction on the new northwest island. As the roundabout design is utilizing the existing accelerate lane, the current through lane will become a new landscaped island, adding green scape to the area. Trenching will also happen during this phase to install electrical for the future pedestrian lights as well as roundabout lighting, as well as stormwater drains. There will be flaggers present during the day and cones will be set up to re-create the existing intersection at night. At the end of this stage there will be a concrete pour for all curbs and islands completed until this point.

Stage 6 – Northern Roundabout Construction



Figure 11 - Stage 6: Northern Roundabout Construction

In order to prepare for the center of the roundabout to be constructed the east approach of Chancellor Boulevard will be closed off for a few days. This closure will span from Western Parkway to Theology Mall and will have one-way traffic on the west approach of Chancellor Boulevard. Also there will not be access to Wesbrook Crescent during this stage. Additional flaggers will be added to the existing site team to ensure the safety of all. During this stage of construction the new northeast island will be prepared as well as the northern half of the roundabout. The east approach of Chancellor Boulevard will also be milled to make way for new asphalt.

Stage 7 – Southern Roundabout Construction




Figure 12 - Stage 7: Southern Roundabout Construction

This stage of construction will be very similar to the last expect the west approach of Chancellor Boulevard will now be closed and one-way traffic will be diverted onto the east approach. Wesbrook Crescent will now be open for access again but Wesbrook Mall will now be closed for access from Chancellor Boulevard. Buses will use Blanc and 16th instead of Chancellor Boulevard. Trenching for electrical and stormwater drains will also happen during this stage as well as milling.

Stage 8 – Electrical Trenching



Figure 13 - Stage 8: Electrical Trenching

During this stage of construction the west approach of Chancellor Boulevard will be closed for Western Parkway to Theology Mall but there will be access to Wesbrook Mall. The final stages of trenching will commence to complete both electrical and stormwater drains. Flaggers will be present during the construction and the existing geometric layout will be recreated with cones during the night. The existing median on either side of the intersection will be modified to create a more channelized approach and exit from the future roundabout

Stage 9 - Roundabout Construction




Figure 14 - Stage 9: Roundabout Construction

During this stage of construction the entire intersection will temporarily be closed. Vehicles including buses will be diverted to Blanca and West 16th Avenue, there will not be access to Wesbrook Mall. There will be adequate construction signs to alert vehicles of the upcoming changes as at night the intersection will open for the first time as a roundabout created with cones. All the concrete will be formed and poured during this stage for the roundabout as well as any curbs or island that have not been completed. This will include reinstalling the curb work at Western Parkway that was temporarily removed for bus accommodations.

Stage 10 – Paving and Painting




Figure 15 - Stage 10: Paving, Painting and Landscaping

Continuing from last stage this final stage will complete the construction process. New asphalt will be placed, the road will be painted, including the bicycle lanes and crosswalks, and landscaping will be completed. Final light posts and signage that had not been completed will be installed and the general contractor will demobilize from site.

Stage 11 – Gateway Installation



Figure 16 - Stage 11: Gateway Installation

Construction of the structural gateway is to begin in the summer following completion of the roundabout. This scheduled date is Monday, April 30, 2018, which marks the first week following the year end for UBC students. The gateway requires 7 weeks to be installed. It is scheduled to be completed and commissioned for use on Thursday, June 14, 2018.

During this phase of construction, a mobile crane is to be stationed on the road enclosing the roundabout. The crane will be needed through all stages of construction. Additionally, prefabricated gateway components will be stored in three main areas: the east median island, the roundabout, and the west median island.

Due to the need for storage space around the roundabout, as well as stationing a crane, this period of construction will require full closure of the roundabout. Flaggers and road signs will be stationed at subsequent major intersections of all roundabout approaches to inform commuters of the lack of access. Busses through the intersection will be diverted to turn at West 16th Avenue and Blanca. Full closure to accommodate gateway installation will last for 7 weeks.

6. COST ESTIMATION

The cost of consultation during pre-construction is approximately \$254,730. The cost of roundabout construction is approximately \$1,479,000. Detailed breakdown of these costs can be found in *Appendix L –Cost Estimate* and a summary can be found below in *Table 14*. The total capital cost is thus estimated to be \$1,733,800.

Annual operating costs are incurred by landscape maintenance. Landscape maintenance is to be carried out weekly by a 2-person crew from UBC building operations. As per UBC building operations’ charge out rates, the annual cost for landscaping is approximately \$15,300 per year.

Table 14 - Summary of Cost Estimate

COST ESTIMATE			
DESIGN			TOTAL: \$254,750
Preliminary Design (Complete)		\$95,600	
Detailed Design		\$116,200	
Contract Administration and Construction Reviews		\$42,950	
CONSTRUCTION			TOTAL: \$1,479,000
General Contractor	\$238,400	Permitting	\$9,900
Concrete	\$62,300	Gateway Structure	\$578,900
Excavation	\$77,800	Utilities	\$120,000
Curbwork	\$6,600	Asphalt	\$92,300
Material Testing	\$10,000	Landscaping	\$26,400
Painting	\$4,000	Signage	\$5,000
Flagging	\$113,000	Fee	\$134,500
ADDITIONAL BUDGETS			
Contingency		\$67,200	
Maintenance		\$15,300 per year	
			TOTAL: \$1,733,800

6.1. Permitting

As per the City of Vancouver’s development permits and regulations, construction of the roundabout is subject to the following permits.

- Electrical
- Tree Removal
- Signage

– Noise

In addition, an allowance for excavation permitting has been incorporated into the estimate to cover costs not directly specified by City of Vancouver's regulations.

30-day parking permits will be issued for all workers on site for the duration of their work on site. These will allow workers to park at the Rose Garden and/or North Parkades. The total cost of permitting is approximately \$9,900.

6.2. Consulting Project-Management

Consulting fees during pre-construction are approximately \$254,730. Fees are based on a 40-hour work week, and assuming that the consulting staff will work half-time specifically on this project.

i. Detailed Design:

- carried out by traffic/road engineer and CAD technician
- project engineer to liaison with client, oversee project costs
- project team supervised by management engineer for progress

ii. Surveying

- carried out by a surveying team to confirm as-builts supplied by UBC

iii. Geotechnical Evaluation

- carried out by geotechnical consultants to assist in design

iv. Final Design

- utilizing data acquired from the surveying and geotechnical team, this stage is carried out by the same project team as the one in detailed design

Contractor Selection and Preparation

- carried out by project engineer and management engineer

Site visits, requests for information, field orders, and other interactions between the contractor and consultant are expected to occur during construction. Since the degree of involvement of the consulting staff is not foreseeable, consulting fees incurred during construction work have not been quantified in this estimate.

6.3. General Contractor

The general contractor shall supply a construction management staff, site equipment, temporary power, and an operations and maintenance manual. For this estimate, the general contractor is assumed to be self-performing on select concrete structures, and erection of the steel gateway structure.

Costs incurred by the general contractor include \$238,400 in indirect costs, and \$62,300 in self-performing concrete work (inclusive of the roundabout and sidewalk structures).

6.4. Subcontractors

As part of their quotes, subcontractors are expected to incorporate a quality control plan for their products. The general contractor will perform quality assurance on the delivered products and services, document results, and submit to the client when complete.

Excavation

The excavation subcontractor is to perform demolition of existing islands, trenching for electrical and stormwater installation, backfilling of excavations, as well as supply transfer trucks to remove excavated material from site.

The subcontractor is to provide a workforce and heavy equipment as deemed necessary by their project staff.

Costs incurred by the excavation subcontractor are approximately \$77,800.

Utilities

Utilities work will be coordinated between an electrical subcontractor and a stormwater subcontractor. The electrical subcontractor is to perform installation of new electrical conduits, as well as fitting of relocated electrical pull pits. The stormwater subcontractor is to perform the same work for existing and new stormwater connections.

A total allowance of \$120,000 has been incorporated into the estimate to account for utilities work. Final quotes for the utilities can be established after detailed design drawings are produced.

Formwork and Concrete

A separate subcontractor generally performs curb formwork and casting. The curb subcontractor will install curbs that line the perimeter of new islands in the intersection. Costs incurred by the curb subcontractor are approximately \$6,600.

Asphalt & Material Testing

The asphalt/paving subcontractor is to perform milling of existing asphalt, and paving of new asphalt on the roads. Costs incurred by the paving subcontractor are approximately \$93,300.

The material testing subcontractor shall perform compaction testing on backfilled excavations and testing of new asphalt. A \$10,000 allowance has been incorporated into the estimate to account for their work.

Landscaping

The landscaping subcontractor is to perform installation of new sub-base, top soil, and grass in the new islands. Costs incurred by the landscaping subcontractor are approximately \$26,400.

Painting

The painting subcontractor is to perform painting of new pedestrian crosswalks. A \$4,000 allowance has been incorporated into the estimate to account for their work.

Signage

Temporary signage is to be performed by subcontracted flaggers. A \$5,000 allowance has been incorporated into the estimate to account for signage during construction.

Flagging

Flaggers are needed throughout the duration of construction. During construction phases 1-5, two flaggers are stationed during active work hours on site. Following that, two more are added to the work crew. Costs incurred by the flagging subcontractor are approximately \$113,000.

6.5. Gateway

The structural gateway to be installed at the roundabout is estimated to cost \$578,900. A summarized breakdown of the gateway’s cost items can be seen in *Table 15* below. Refer to *Appendix L –Cost Estimate* for further cost details regarding the gateway.

Table 15 - Summary of Gateway Cost

GATEWAY CONSTRUCTION		TOTAL: 578,900	
<i>General Contractor</i>	<i>84,000</i>	<i>Permitting</i>	<i>4,000</i>
<i>Flagging</i>	<i>36,800</i>	<i>Mobile Crane</i>	<i>61,600</i>
<i>Grass Rehabilitation</i>	<i>5,000</i>	<i>Grass Protection</i>	<i>5,800</i>
<i>Concrete Foundation</i>	<i>162,400</i>	<i>Moisture Protection</i>	<i>8,000</i>
<i>Gateway - Concrete</i>	<i>11,100</i>	<i>Gateway - Wood</i>	<i>46,400</i>
<i>Gateway - Steel</i>	<i>103,500</i>	<i>Gateway - Railings</i>	<i>50,200</i>

6.6. Contingency

A contingency fee of 5% of the construction cost has been incorporated into the estimate. For the roundabout, contingency is valued at \$67,200. This fee will account for circumstances such as:

- i. Unknown conditions
 - Surveyor’s as-builts do not match client-provided as-builts, resulting in errors in takeoffs
 - Unsuitable soil conditions following geotechnical evaluation, which requires additional work not accounted for in the original excavation scope
- ii. Client-requested modifications
 - UBC wishes to incorporate more green space than what was issued in the construction drawings
 - UBC adjusts site working hours to reduce noise pollution
- iii. Consultant modifications
 - Newly issued details from consultant require different grade of sub-base to be used to backfill perforated drainage pipes
 - New field orders from consultant require stormwater tie-ins to be completed before installation of a new electrical pull pit, altering the construction schedule

Works Cited

- BC Ministry of Transportation. (2000). Manual of Standard Traffic Signs & Pavement Markings. Engineering Branch. Vancouver: British Columbia Ministry of Transportation and Highways.*
- Campus and Community Planning. (2014). UBC Transportation Plan: Vancouver Campus. Vancouver: The University of British Columbia.*
- Campus and Community Planning. (2016). Land Use and Permitting (Policy 92). Retrieved November 2016, from Campus + Community Planning: <http://planning.ubc.ca/vancouver/planning/land-use-and-permitting-policy-92>*
- Engineering Services. (2008). Street Restoration Manual. Departmental Services. Vancouver: The City of Vancouver.*
- Environmental Mechanics Alberta . (2016). Cone Penetration Tests. Retrieved February 27, 2017, from Environmental Mechanics Alberta Website: <http://www.envi.se/products/cpt/>*
- Kittelson & Associates Inc. . (2014). Kansas Roundabout Guide . Kansas: Kansas Department of Transportation .*
- Ministry of Transportation and Infrastructure. (2015). Traffic Management Manual for Work on Roadways. Vancouver: Government of British Columbia.*
- Nyland, D. (2007). BC Supplement to TAC Geometric Design Guide. Ministry of Transportation, Engineering Branch. Vancouver: British Columbia Ministry of Transportation.*
- The City of Vancouver . (2016). Street Construction Standards . Retrieved November 2016, from The City of Vancouver : <http://vancouver.ca/streets-transportation/construction-standards.aspx>*
- UBC Sustainability. (2014). 20-Year Sustainability Strategy: For The University of British Columbia Vancouver Campus. Vancouver: The University of British Columbia.*
- WorkSafeBC. (2016). OHS Regulation & Related Materials. Retrieved November 2016, from WorkSafeBC: <https://www.worksafebc.com/en/law-policy/occupational-health-safety/searchable-ohs-regulation>*

Appendix A – Conceptual Design Alternatives

Alternative to the design of a roundabout, two other designs were considered during the conceptualization of the new intersection:

1. Signalized Intersection
2. Retain and Improve the Existing Intersection

This section will briefly describe the alternative concepts to upgrading the intersection. To select the design moving forward, a decision matrix was utilized, please see *Figure 19* and *Figure 20* for further details.

Signalized Intersection




Figure 17 - Signalized Intersection: AutoCAD Layover

One alternative provided a pedestrian safety focused design concept; the signalized intersection concept proposed to implement signalized traffic signals on all approaches of the intersection, with minor road re-alignments. Implementing signalized pedestrian crosswalks on all directions will also provide a protected and guided pedestrian crossing system. Bicycle lanes are also designed to be integrated with road traffic, similar to other intersections and bicycle roads around UBC. The signalized intersection provides more capacity for heavy vehicles, pedestrians, and cyclists.

Retain and Improve the Existing Intersection




Figure 18 - Proposed Upgrades to Existing Intersection: AutoCAD Layover

A second alternative provided a cost and time effective design concept; the intersection is proposed to retain existing geometry. The concept proposed the addition of signalized pedestrian sidewalks with minor realignments of traffic islands, as well as redesign of the existing stormwater management system. Furthermore, a sidewalk was designed to connect all pedestrian approaches. The design highlights the possibility to satisfy most key design requirements with minimal cost and construction delays, however does not improve traffic capacity. The design however is more flexible and allows for less project risk whilst still capable of addressing the current issues.




Figure 19 - Criteria Weight for Decision Process




Figure 20 - Weighted Scores for Decision Making Process

Appendix B – Presentation Slides



Project Objectives


Upgrade works for the current intersection at Chancellor Boulevard and Wesbrook Mall, UBC

Design Objectives

- Safety
- Vehicular Traffic Accommodation
- Sustainability
- Structural Gateway


Key Design Components

- Roundabout
- Bike Lanes
- Pedestrian Crossings
- Sidewalk along southeast side
- Stormwater Re-provisioning
- Gateway Structure



Software Packages and Standards

- AutoCAD
- SYNCHRO
- AutoTURN
- SketchUp
- SAP2000
- NBCC 2010
- BCBC
- ASTM



Technical Considerations - Roundabout

- Satisfactory LOS (Level of Service) performance under current and future conditions
- Accommodation of heavy vehicles
- Provide improved pedestrian safety; right-of-way's




Design Outputs - Traffic Operations

AM Peak 2016



AM Peak 2040



Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Dark Blue	5 to 10
Light Blue	10 to 15
Yellow	15 to 25
Orange	25 to 40
Red	40 to 60
Pink	>= 60

- 2016: LOS B at all approaches
- 2040: LOS B at west and south approach, LOS F at east approach

Design Outputs - Traffic Operations

AM Peak 2016



AM Peak 2040



Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Dark Blue	5 to 10
Light Blue	10 to 15
Yellow	15 to 25
Orange	25 to 40
Red	40 to 60
Pink	>= 60

- 2016: LOS A at all approaches
- 2040: LOS B at west and east approach, LOS A at south approach

Gateway Design Concept



Gateway Considerations

A gateway to provide an entrance to campus, and a significant structural landmark for campus


Features

- Open Walkway and Viewing Platform
- Historical Exhibit Room
- UBC Logo

Material & Design

- Open steel walkway and frame
- Steel staircase
- Wooden enclosed structure above roundabout





COST ESTIMATE	
DESIGN	TOTAL: \$254,750
Preliminary Design (Complete)	\$95,600
Detailed Design	\$116,200
Contract Administration and Construction Reviews	\$42,950
CONSTRUCTION	TOTAL: \$1,547,400
General Contractor	\$227,000
Subcontracted Work	\$538,800
Gateway Structure	\$641,000
Fee	\$140,600
ADDITIONAL BUDGETS	
Contingency	\$70,300
Maintenance	\$17,300 per year
	TOTAL: \$1,872,450

Construction Work

Considerations and sequencing


May – August 2017

Gateway: April – June 2018



Construction Requirements

Requirement	Solution
<ul style="list-style-type: none"> Intersection bus routes need to be serviceable throughout construction 	<ul style="list-style-type: none"> Roundabout construction offers partial route through intersection; temp detours planned during full intersection close-off
<ul style="list-style-type: none"> Noise disturbance 	<ul style="list-style-type: none"> Number of heavy machinery on site kept to a minimum
<ul style="list-style-type: none"> Construction period should not overlap with academic period 	<ul style="list-style-type: none"> Beginning of major paving to coincide with U-Hill Elementary's summer vacation Roundabout construction wrapped up before UBC's fall 2017 semester begins



Anticipated Site Issues

- Unknown depth of existing utilities
 - Avoid fish routes
- Limited storage area
- Traffic management



Additional Data and Tests

- Surveying - Specifically property lines at the new sidewalk
- CPT - for the Gateway
- Scanning - Utility Depths and Locations
- Soil Samples - Bearing Capacity



Stage 1 - Mobilization



May 1 - 2

2 Days

Stage 2 - Southwest Island Demolition



May 2 - 4

2 Days

Stage 3 – South East Island Demolition



May 4 - 8

2 Days

Temporary Bus Accommodation



May 8 - 10

2 Days

Stage 4 – North East Median Construction



May 11 - 22

7.5 Days

Stage 5 – North West Median Construction



May 22 -
June 8

13 Days

Stage 6 – Northern Roundabout Construction



June 8 - 19

7 Days

Stage 7 – Southern Roundabout Construction



June 19 -
July 3

10.5 Days

Stage 8 – Electrical Trenching



July 3 -
July 14

9 Days

Stage 9 – Roundabout Construction



July 14 - 25

8 Days

Stage 10 – Paving, Painting, Landscaping



July 25 -
Aug 9

11 Days

Stage 11 – Gateway Structure



Apr 30 –
Jun 12
2018

32 Days

Appendix C – Stakeholder Register


Stakeholder Register

Stakeholder ID/Name	Power Score 1-5	Level of Concern		Management Category	Position	Expectation and Role
		Direct Control, Influence	Technical, Nontechnical			
	Score: 1-5	Score: T or N	Score: D, or W or M or I	Score: S or N or R	What Role Does the Stakeholder Have Regarding the Project?	What Does This Stakeholder Want?
A UBC Campus and Community Planning	5	T	D	S	Supporter	University Oversight, UBC Regulations
B Ministry of Transportation	5	T	W	S	Neutral	Design Approval, Ownership, Regulations
C Musqueam	5	N	I	N	Resister	Land Close to Project
D UBC Students	3	N	I	R		Construction Interference Concern
E University Endowment Lands	5	N	W	N		Construction Interference Concern, Owns Property Close to Project
F City of Vancouver	5	T	W	N		Interference with Current Traffic Routes, Re-Alignment of Drainage Systems
G Pedestrians	4	N	I	S		User, New crosswalk and Markings to Ensure Safe Crossing
H Cyclists	4	N	I	S		User, Additional safety features to isolate vehicular traffic
I TransLink	4	T	W	R		User, Construction interference with current traffic routes
J Neighbour Residents	5	N	I	R		Construction interference concern, Owns property close to project land
K Consultants	5	T	D	N		Design, Environmental Assessment, Engineering, Technical Specifications
L General Contractor	5	T	D	S		Building Specifications, Schedule, Budget, Scope, Permits, Labour

Appendix D – Drawing Package

Civil Drawing

Structural Drawing



LEGEND

□ HSS COLUMN 89x89x640

○ COLUMN

REFERENCE:

FILE NO.: -

REVISIONS:

A.

B.

C.

DWG. NO.: S-1

UBC ROUNDABOUT UPGRADE
 WESBROOK MALL & CHANCELLOR BLVD.
 GATEWAY - STRUCTURAL


DATE: 3-24-2017

DRAWN BY: MC

APPROVED BY: -

REMOVED BY: -

SCALE: NOT TO SCALE



REFERENCE:

FILE NO.:	-	REVISIONS:
DWG. NO.:	2	A.
		B.
		C.


UBC ROUNDABOUT UPGRADE
 WESBROOK MALL & CHANCELLOR BLVD.
 GATEWAY - STRUCTURAL

DATE:	4-01-2017
DRAWN BY:	MG
APPROVED BY:	-
REVIEWED BY:	-
SCALE:	NOT TO SCALE

HSS COLUMN
89x89x6400

32 MPA CONCRETE

1.0 METER
SQUARE FOOTING



REFERENCE:


DATE:	4-01-2017		
DRAWN BY:	MG	APPROVED BY:	-
SCALE:	NOT TO SCALE		

UBC ROUNDABOUT UPGRADE
WESBROOK MALL & CHANCELLOR BLVD.
FOUNDATION PROFILE

FILE NO.:	-	REVISIONS:	A.
DWG. NO.:	S-3		B.
			C.

Mechanical Drawing

NOTES:
 ALL DETAILS AS PER MMCD.
 REFER TO EXISTING LAYOUTS BEFORE CONSTRUCTION.
 SUBMIT ALL SHOP DRAWINGS PRIOR TO MATERIAL PURCHASE.
 REFER TO SCHEDULE FOR TIMELINE OF WORK.



LEGEND:
 ○ STORM WATER MANHOLE
 ▨ STORM WATER CATCH BASIN
 — STORM WATER MAIN

REFERENCE:


FILE NO.:	—	REVISIONS:
DWG. NO.:	M-1	A.
		B.
		C.

UBC ROUNDABOUT UPGRADE
WESBROOK MALL & CHANCELLOR BLVD.

DATE:	03-19-2017
DRAWN BY:	RL
APPROVED BY:	—
REVIEWED BY:	JF
SCALE:	1:500

Electrical Drawing

NOTES:
 ALL DETAILS AS PER MMCD.
 REFER TO EXISTING LAYOUTS BEFORE CONSTRUCTION.
 SUBMIT ALL SHOP DRAWINGS PRIOR TO MATERIAL PURCHASE.
 REFER TO SCHEDULE FOR TIMELINE OF WORK.



LEGEND:
 ☆ STREET LIGHT
 * CROSSWALK BEACON
 □ ELECTRICAL BOX
 — POWER MAIN


















REFERENCE

DATE:	03-19-2017	
DRAWN BY:	APPROVED BY:	REVIEWED BY:
RL	-	JF
SCALE:	1:500	

UBC ROUNDABOUT UPGRADE
 WESBROOK MALL & CHANCELLOR BLVD.


















FILE NO.:	-	REVISIONS:
DWG. NO.:	E-1	A.
		B.
		C.


Appendix E – Traffic Analysis Results (Synchro)

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Sign Control		Stop			Stop			Stop			Stop	
Volume (vph)	0	126	77	437	0	0	0	72	116	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	137	84	475	0	0	0	78	126	0	0	0
Direction, Lane #	EB 1	EB 2	WB 1	NB 1	NB 2							
Volume Total (vph)	137	84	475	78	126							
Volume Left (vph)	0	0	475	0	0							
Volume Right (vph)	0	84	0	0	126							
Hadj (s)	0.03	-0.55	0.23	0.07	-0.31							
Departure Headway (s)	4.7	3.2	4.5	5.4	3.2							
Degree Utilization, x	0.18	0.07	0.60	0.12	0.11							
Capacity (veh/h)	737	1121	785	593	1121							
Control Delay (s)	8.7	6.5	14.0	9.1	6.6							
Approach Delay (s)	7.8		14.0	7.6								
Approach LOS	A		B	A								
Intersection Summary												
Delay			11.0									
HCM Level of Service			B									
Intersection Capacity Utilization			52.1%		ICU Level of Service		A					
Analysis Period (min)			15									


HCM Unsignalized Intersection Capacity Analysis
5: Chancellor Boulevard & Wesbrook Mall

2016 Existing PM Peak
2016-11-18


















												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Sign Control		Stop			Stop			Stop			Stop	
Volume (vph)	0	365	80	96	0	0	0	53	243	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	397	87	104	0	0	0	58	264	0	0	0
Direction, Lane #	EB 1	EB 2	WB 1	NB 1	NB 2							
Volume Total (vph)	397	87	104	58	264							
Volume Left (vph)	0	0	104	0	0							
Volume Right (vph)	0	87	0	0	264							
Hadj (s)	0.02	-0.57	0.56	0.07	-0.52							
Departure Headway (s)	4.2	3.2	5.0	5.1	3.2							
Degree Utilization, x	0.46	0.08	0.15	0.08	0.23							
Capacity (veh/h)	842	1121	693	644	1122							
Control Delay (s)	10.8	6.5	8.9	8.5	7.2							
Approach Delay (s)	10.0		8.9	7.4								
Approach LOS	A		A	A								
Intersection Summary												
Delay			9.0									
HCM Level of Service			A									
Intersection Capacity Utilization			42.8%	ICU Level of Service	A							
Analysis Period (min)			15									



Movement	EBT	EBR	WBL	WBT	NBL	NBR
Right Turn Channelized						
Volume (veh/h)	126	77	437	412	72	116
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	137	84	475	448	78	126
Approach Volume (veh/h)	221			923	204	
Crossing Volume (veh/h)	475			78	137	
High Capacity (veh/h)	952			1303	1244	
High v/c (veh/h)	0.23			0.71	0.16	
Low Capacity (veh/h)	771			1087	1033	
Low v/c (veh/h)	0.29			0.85	0.20	
Intersection Summary						
Maximum v/c High				0.71		
Maximum v/c Low				0.85		
Intersection Capacity Utilization	81.2%			ICU Level of Service	D	




















Movement	EBT	EBR	WBL	WBT	NBL	NBR
Right Turn Channelized						
Volume (veh/h)	372	82	98	109	54	248
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	404	89	107	118	59	270
Approach Volume (veh/h)	493			225	328	
Crossing Volume (veh/h)	107			59	404	
High Capacity (veh/h)	1274			1323	1007	
High v/c (veh/h)	0.39			0.17	0.33	
Low Capacity (veh/h)	1061			1105	820	
Low v/c (veh/h)	0.47			0.20	0.40	
Intersection Summary						
Maximum v/c High			0.39			
Maximum v/c Low			0.47			
Intersection Capacity Utilization			65.1%		ICU Level of Service	C

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Sign Control		Stop			Stop			Stop			Stop	
Volume (vph)	0	203	124	703	0	0	0	116	187	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	221	135	764	0	0	0	126	203	0	0	0
Direction, Lane #	EB 1	EB 2	WB 1	NB 1	NB 2							
Volume Total (vph)	221	135	764	126	203							
Volume Left (vph)	0	0	764	0	0							
Volume Right (vph)	0	135	0	0	203							
Hadj (s)	0.03	-0.55	0.23	0.07	-0.31							
Departure Headway (s)	5.2	3.2	4.9	6.2	3.2							
Degree Utilization, x	0.32	0.12	1.03	0.22	0.18							
Capacity (veh/h)	674	1121	747	560	1121							
Control Delay (s)	10.7	6.6	62.7	11.0	6.9							
Approach Delay (s)	9.1		62.7	8.5								
Approach LOS	A		F	A								
Intersection Summary												
Delay			37.2									
HCM Level of Service			E									
Intersection Capacity Utilization			70.3%		ICU Level of Service			C				
Analysis Period (min)			15									


HCM Unsignalized Intersection Capacity Analysis
5: Chancellor Boulevard & Wesbrook Mall

2040 Existing PM Peak
2016-11-18

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Sign Control		Stop			Stop			Stop			Stop	
Volume (vph)	0	598	132	158	0	0	0	87	399	0	0	0
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	0	650	143	172	0	0	0	95	434	0	0	0
Direction, Lane #	EB 1	EB 2	WB 1	NB 1	NB 2							
Volume Total (vph)	650	143	172	95	434							
Volume Left (vph)	0	0	172	0	0							
Volume Right (vph)	0	143	0	0	434							
Hadj (s)	0.02	-0.57	0.56	0.07	-0.52							
Departure Headway (s)	4.4	3.2	5.5	5.9	3.2							
Degree Utilization, x	0.80	0.13	0.26	0.15	0.39							
Capacity (veh/h)	796	1121	630	569	1114							
Control Delay (s)	22.9	6.7	10.4	9.9	8.2							
Approach Delay (s)	19.9		10.4	8.5								
Approach LOS	C		B	A								
Intersection Summary												
Delay			14.8									
HCM Level of Service			B									
Intersection Capacity Utilization			64.7%		ICU Level of Service		C					
Analysis Period (min)			15									



Movement	EBT	EBR	WBL	WBT	NBL	NBR
Right Turn Channelized						
Volume (veh/h)	203	124	703	663	116	187
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	221	135	764	721	126	203
Approach Volume (veh/h)	355		1485		329	
Crossing Volume (veh/h)	764		126		221	
High Capacity (veh/h)	755		1255		1165	
High v/c (veh/h)	0.47		1.18		0.28	
Low Capacity (veh/h)	597		1043		962	
Low v/c (veh/h)	0.60		1.42		0.34	
Intersection Summary						
Maximum v/c High			1.18			
Maximum v/c Low			1.42			
Intersection Capacity Utilization			121.8%		ICU Level of Service	H



Movement	EBT	EBR	WBL	WBT	NBL	NBR
Right Turn Channelized						
Volume (veh/h)	598	132	158	175	87	399
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Hourly flow rate (vph)	650	143	172	190	95	434
Approach Volume (veh/h)	793			362	528	
Crossing Volume (veh/h)	172			95	650	
High Capacity (veh/h)	1211			1286	828	
High v/c (veh/h)	0.66			0.28	0.64	
Low Capacity (veh/h)	1003			1072	661	
Low v/c (veh/h)	0.79			0.34	0.80	
Intersection Summary						
Maximum v/c High	0.66					
Maximum v/c Low	0.80					
Intersection Capacity Utilization	98.0%			ICU Level of Service	F	

Appendix F – Traffic Analysis Results (SimTraffic)

Delays – Morning (AM) 2016

Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Teal	5 to 10
Green	10 to 15
Light Green	15 to 25
Yellow	25 to 40
Red	40 to 60
Pink	>= 60

Figure 21 - Legend for Delays per Vehicle



Figure 22 - Delays: 2016 AM Existing Intersection



Figure 23 - Delays: 2016 AM Proposed Roundabout

Queues – Morning (AM) 2016




Queue Lengths All Intervals	
Color	Queue Type
	Average
	95th Percentile
	Max Observed

Figure 24 - Legend for Queues




Figure 25 - Queues: 2016 AM Existing Intersection



Figure 26 - Queues: 2016 AM Proposed Roundabout

Delays – Afternoon (PM) 2016

Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Teal	5 to 10
Light Green	10 to 15
Yellow-Green	15 to 25
Yellow	25 to 40
Red	40 to 60
Pink	>= 60

Figure 21 - Legend for Delays per Vehicle



Figure 27 - Delays: 2016 PM Existing Intersection



Figure 28 - Delays: 2016 PM Proposed Roundabout

Queues – Afternoon (PM) 2016




Queue Lengths All Intervals	
Color	Queue Type
	Average
	95th Percentile
	Max Observed

Figure 24 - Legend for Queues



Figure 29 - Queues: 2016 PM Existing Intersection



Figure 30 - Queues: 2016 PM Proposed Roundabout

Delays – Morning (AM) 2040

Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Teal	5 to 10
Green	10 to 15
Light Green	15 to 25
Yellow	25 to 40
Red	40 to 60
Pink	>= 60

Figure 21 - Legend for Delays per Vehicle



Figure 31 - Delays: 2040 AM Existing Intersection



Figure 32 - Delays: 2040 AM Proposed Roundabout

Queues – Morning (AM) 2040




Queue Lengths All Intervals	
Color	Queue Type
	Average
	95th Percentile
	Max Observed

Figure 24 - Legend for Queues



Figure 33 - Queues: 2040 AM Existing Intersection



Figure 34 - Queues: 2040 AM Proposed Roundabout

Delays – Afternoon (PM) 2040

Delays / Vehicle All Intervals	
Color	seconds
Black	< 5
Teal	5 to 10
Green	10 to 15
Yellow-Green	15 to 25
Yellow	25 to 40
Red	40 to 60
Pink	>= 60

Figure 21 - Legend for Delays per Vehicle



Figure 35 - Delays: 2040 PM Existing Intersection



Figure 36 - Delays: 2040 PM Proposed Roundabout

Queues – Afternoon (PM) 2040




Queue Lengths All Intervals	
Color	Queue Type
	Average
	95th Percentile
	Max Observed

Figure 24 - Legend for Queues



Figure 37 - Queues: 2040 PM Existing Intersection




Figure 38 - Queues: 2040 PM Proposed Roundabout

Appendix G – Sample Roundabout Calculation

Roundabout Sample Calculations

Stopping sight distance:

$$d = 1.47(t)(V) + 1.075 \left(\frac{V^2}{a} \right) = 1.47(2.5)(31) + 1.075 \left(\frac{31^2}{11.2} \right) = 270 \text{ ft} = 82 \text{ m}$$

t = reaction time, assumed to be 2.5 seconds

V = approach speed, taken to be 50 km/h approaching roundabout, 31 mph

a = deceleration rate, 11.2 ft/s² (Kittelson & Associates Inc. , 2014)

Intersection sight distance:

$$d_1 = 1.47(V_{major,entering})(t_c) = 1.47(31)(5) = 227 \text{ ft} = 69 \text{ m}$$

$$d_2 = 1.47(V_{major,circulating})(t_c) = 1.47(21)(5) = 154 \text{ ft} = 47 \text{ m}$$

d₁ = entering leg of sight triangle length, ft

d₂ = circulating leg of sight triangle length, ft

t_c = critical headway for entering the major road




Figure 39 - Intersection Sight Distance
(Kittelson & Associates Inc. , 2014)

Appendix H – Sample Gateway Calculations

Observation Structure Sample Calculations

Dead Load

- Steel Columns
- Concrete Topping
- Steel Beams, Girders and Decks
- CLT Flooring
- Glass Panels
- Guardrails
- Glulam Columns, Beams

Live Load

Assembly Area 4.8kPa

Snow Load

$$I_s(S_s(C_b C_e C_a) + S_r) = 1.64kPa$$

Variable	Value	Units	Description
I_s	1	Unit less	Importance Factor
C_b	0.8	Unit less	Basic Roof Snow Factor
C_e	1	Unit less	Roof Slope Factor
S_s	1.8	kPa	Snow Loading
S_r	0.2	kPa	Rain Loading

Wind Load

$$I_w q C_e C_g C_p = 0.84kPa$$

Variable	Value	Units	Description
I_w	0.8	Unit less	Importance Factor
q	0.36	Unit less	Wind Loading
C_e	0.93	Unit less	$\frac{h}{10}^{0.2}$ Exposure Factor
C_g	2.5	Unit less	Gust Factor - For Small Structures
C_p	1.0	Unit less	External Pressure Coefficient

Seismic (Walkway)

$$\frac{S_a(2.0)M_v I_e W}{R_d R_0} = 22.5kN$$

Variable	Value	Units	Description
$S_a(2.0)$	0.17	Unit less	Spectral Acceleration, T=2s
M_v	1	Unit less	Higher Mode Effect Factor - Ductile Moment Frame
I_e	1	Unit less	Importance Factor
W	940	kN	Walkway Dead Load
R_d	4	Unit less	Force Modification Factor (Ductility) - Moment Frame
R_0	1.7	Unit less	Force Modification Factor (Over strength) - Moment Frame

Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	1
Subject	Observation Deck (CLT)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016

i) **Loads**

NBCC 2010

Total Load 8.18 kPa (*CLT = 450kg/m3*)

Tributary Width 7.20 m

Factored Load 58.93 kN/m

Mf 381.85 kNm **OK**

Vf 212.14 kN

ii) **CLT Panel**

Layers: 5 Nos. @ Stress Grade E2

(Longitudinal) 3 Nos.

(Transverse) 2 Nos.

Height or Length 7200 mm

Layer Thickness 35 mm

Width 7200 mm

Elong 10300 MPa

Etrans 10000 MPa

Area of 1 Layer 252000 mm²

Layer		Long.		Trans.	
1	y2	0	mm	y2	1225 mm
2	y2	4900	mm	y2	1225 mm
3	y2	4900	mm	y2	mm
4	y2		mm	y2	mm
5	y2		mm	y2	mm
6	y2		mm	y2	mm

8.4.3

Bending Resistance

$M_r = 0.9F_b S_{eff,y} K_{rb,y}$ (*All layers effective in Major Axis*)

Fb 23.9 MPa

S_{eff,y} 29353378.64 mm³

K_{rb,y} 0.85

8.4.3.1

$\sum EI_x$ 8.12053E+11 Nmm²

$\sum EAy^2$ 2.56427E+13 Nmm²

(EI)_{eff} 2.64547E+13 Nmm²

Mr = 536.7 kNm

Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	2
Subject	Deck Design (GL 3 - 4)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016

Deck Girder (GL B, 3-4)

Deck Width w	2	m
Deck Span l	14	m

DL:

Guardrails		0.07 kN/m
1 1/2" Concrete Topping		0.9 kPa

LL:

Assembly		4.8 kPa
Guardrails		1.5 kN/m

SL:

Snow Loading		1.64 kPa
--------------	--	----------

Load combination 3:


1.25DL + 1.5LL + 0.5S		9.1 kPa
Tributary Width		1 m
Total Factored UDL:		11.5 kN/m
Mf		281.8 kNm
Vf		80.5 kN

Deflection Criteria

L/240	58.3	DL+LL
L/360	38.9	LL


W360x134

Mr	806	kNm
Vr	425	kN
Defl. DL + LL	43.8	mm
Defl. LL	37.9	mm




Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	3
Subject	Deck Design (GL 3 - 4)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016


Deck Girder



Bending



Shear



Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	4
Subject	Deck Design (GL 3 - 4)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016

Deck Span Bracing (Lateral Stability and Torsional Stiffness)

Brace length	2	m
Brace spacing	3	m
<u>DL:</u>		
1/2" Concrete Topping		0.9 kPa
<u>LL:</u>		
Assembly		4.8 kPa
<u>SL:</u>		
Snow Loading		1.64 kPa
<u>Load combination 3:</u>		
1.25DL + 1.5LL + 0.5S		9.1 kPa
Tributary Width		3 m
Total Factored UDL:		27.4 kN/m
Mf		30.9 kNm
Vf		41.2 kN

W360x33

Mr	170	kNm	OK
Vr	335	kN	OK
Defl. DL + LL	8.3	mm	OK
Defl. LL	5.6	mm	OK

Steel Column (B3) Supporting Steel Deck


Deck Load	80	kN
Load Case 3	8.7	kPa
Staircase Trib.	2.4	m
Staircase Loading	20.88	kN
Pf	100.88	kN

HSS 89x89x6.4


Pr	101	kN	OK
----	-----	----	-----------

Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	5
Subject	Staircase Landing Beam (GL 2)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016


Staircase Landing Beam



Bending Moment



Shear




Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	6
Subject	Deck Lateral Supporting Frame (GL 2)	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016

Cross Bracing Design

Seismic Loading 23.5 kN
per frame 11.75 kN

Factored Load 20 kN
(Compressive and Tensile)



L76x76x7.9

Compressive Resistance


$$Cr = 0.9AF_y(1+H^{2n})^{-1/n}$$

A	1150	mm ²
F _y	480	30.3
L	6300	mm
r	23.4	mm
F _e	27.23205	MPa
H	4.198367	


Cr 27.74 kN

OK

Axial Force



Bending Moment



Project	Intersection Redesign - Capstone	Date	20-Mar-17
Location	UBC	Page	7
Subject	Lateral Brace Connection	Code	NBCC 2010
By	Group 16	Design	CSA-086-2016

Bolted Brace Connection (Tensile Resistance of Brace Member)

i) **Tensile Resistance**

$$Tr = 0.9 * Ag * Fy$$

Ag 1150 Fy 350 Mpa

Tr 362.3 kN 

ii) **Block Shear Tear Out**

$$Tr = 0.75(UtAnFu + 0.6Agv(Fy+Fu/2))$$

Ut 0.6

An 174.68 mm² (22M dia. * 7.9mm thickness)

Agv 1111.6 mm² 2*(2*35mm spacing * 7.9mm thickness)

Fy 350 Mpa

Fu 480 MPa

Tr 245.3 kN 

iii) **Tensile Fracture Resistance**

$$Tr = 0.75 * Ane * Fu$$

Fu 450 Mpa

Ane 585 mm² (0.6*(Ag- bolt dia. * thickness))

S. Lag 0,6

Tr 197.5 kN 

iv) **Bolt Tensile Resistance**


$$Tr = 0.75*0.8*Ab*Fu$$

Ab 380.1 mm²

Fu 830 Mpa

Tr 189.3 kN 

Appendix I – Construction Schedule: Phase 1 - Roundabout



Project Roundabout Construct Date: Thu 3/2/17


ID	Task Name	Duration	Start	Finish	January 2017	February 2017	March 2017	April 2017	May 2017	June 2017	July 2017	August 2017	September 2017
21	Set up flaggers, work perimeter, temp signs	0 days	Tue 5/2/17	Tue 5/2/17					5/2				
22	Remove existing island and truck out debris	1 day	Wed 5/3/17	Wed 5/3/17									
23	Fill to grade with road base	1 day	Thu 5/4/17	Thu 5/4/17									
24	3 - SE Island Demo	2 days	Thu 5/4/17	Mon 5/8/17									
25	Set up flaggers, work perimeter, temp signs	0 days	Thu 5/4/17	Thu 5/4/17					5/4				
26	Remove existing island and truck out debris	1 day	Fri 5/5/17	Fri 5/5/17									
27	Fill to grade with road base	1 day	Mon 5/8/17	Mon 5/8/17									
28	3.5 - Temporary Bus	2 days	Mon 5/8/17	Wed 5/10/17									
29	Set up flaggers, work perimeter, temp signs	0 days	Mon 5/8/17	Mon 5/8/17									
30	Cut back curbs on next	1.5 days	Tue 5/9/17	Wed 5/10/17									
31	Fill to grade with road base	0.5 days	Wed 5/10/17	Wed 5/10/17									
32	4 - NE Median Construction	7.5 days	Thu 5/11/17	Mon 5/22/17									
33	Mob additional fence; set up flaggers, work perimeter, temp signs	0.5 days	Thu 5/11/17	Thu 5/11/17									
34	Cut back on extg island	1 day	Thu 5/11/17	Fri 5/12/17									
35	Formwork on new curbs on	1.5 days	Thu 5/11/17	Fri 5/12/17									
36	Excavate/trench to relocate extg drainage pipe	1.5 days	Fri 5/12/17	Mon 5/15/17									
37	Backfill drainage pipe	0.5 days	Tue 5/16/17	Tue 5/16/17									
38	Excavate/trench to install new electrical boxes	2 days	Tue 5/16/17	Thu 5/18/17									

Project Roundabout Construct
Date: Thu 3/2/17

Task Summary Milestone Critical

Page 2

ID	Task Name	Duration	Start	Finish
39	Backfill electrical boxes	1 day	Thu 5/18/17	Fri 5/19/17
40	Fill cut island to grade with road base	1 day	Fri 5/19/17	Mon 5/22/17
41	5 - NW Median Construction	13 days	Mon 5/22/17	Thu 6/8/17
42	Set up flaggers, work perimeter, temp signs	0 days	Mon 5/22/17	Mon 5/22/17
43	Cut back on extg island	1 day	Mon 5/22/17	Tue 5/23/17
44	Excavate/trench to relocate extg electrical box	2 days	Tue 5/23/17	Thu 5/25/17
45	Backfill electrical box	1 day	Thu 5/25/17	Fri 5/26/17
46	Excavate/trench to install new stormwater and electrical	2 days	Fri 5/26/17	Tue 5/30/17
47	Backfill to grade with road base	1 day	Tue 5/30/17	Wed 5/31/17
48	Excavate for new westbound	3 days	Wed 5/31/17	Mon 6/5/17
49	Backfill to grade with road base	1 day	Mon 6/5/17	Tue 6/6/17
50	Formwork prep	1 day	Mon 5/22/17	Tue 5/23/17
51	Formwork install	1 day	Mon 6/5/17	Tue 6/6/17
52	Pour curbs on phase 4 and 5 islands	1 day	Tue 6/6/17	Wed 6/7/17
53	Strip curbs	1 day	Wed 6/7/17	Thu 6/8/17
54	6 - Northern Roundabout Construction	7 days	Thu 6/8/17	Mon 6/19/17
55	Mob additional fence; set up flaggers, work perimeter, temp signs	0.5 days	Thu 6/8/17	Thu 6/8/17
56	Excavate for new northern half of	1 day	Fri 6/9/17	Fri 6/9/17



ID	Task Name	Duration	Start	Finish	Jan 2017	Feb 2017	Mar 2017	Apr 2017	May 2017	June 2017	July 2017	August 2017	Septem
57	Fill roundabout to grade with road base	1 day	Mon 6/12/17	Mon 6/12/17									
58	Excavate for new island to 0.5 days	1 day	Tue 6/13/17	Tue 6/13/17									
59	Fill new island to 0.5 days grade with road base	0.5 days	Wed 6/14/17	Wed 6/14/17									
60	Milling top coat for new asphalt	3 days	Wed 6/14/17	Mon 6/19/17									
61	7 - Southern Roundabout Construction	10.5 days	Mon 6/19/17	Mon 7/3/17									
62	Set up flaggers, work perimeter, temp signs	0 days	Mon 6/19/17	Mon 6/19/17									
63	Milling top coat for new asphalt	3 days	Mon 6/19/17	Thu 6/22/17									
64	Excavate and trench south	2 days	Thu 6/22/17	Mon 6/26/17									
65	Tie in electrical	1 day	Mon 6/26/17	Tue 6/27/17									
66	Tie in drainage	3 days	Tue 6/27/17	Fri 6/30/17									
67	Backfill to grade with road base	1 day	Mon 7/3/17	Mon 7/3/17									
68	Excavate for new sidewalk	1 day	Mon 6/26/17	Tue 6/27/17									
69	Formwork prep	1 day	Mon 6/26/17	Tue 6/27/17									
70	Formwork install and pack on new curbs	1 day	Tue 6/27/17	Wed 6/28/17									
71	Pour sidewalk	0.5 days	Wed 6/28/17	Wed 6/28/17									
72	Strip sidewalk	0.5 days	Thu 6/29/17	Thu 6/29/17									
73	Excavate for new southern half of	1 day	Tue 6/27/17	Wed 6/28/17									
74	Backfill roundabout to grade with road base	1 day	Wed 6/28/17	Thu 6/29/17									
75	Excavate for channelized island addition	0.5 days	Thu 6/29/17	Thu 6/29/17									
76	Curb formwork prep	0.5 days	Thu 6/29/17	Thu 6/29/17									


ID	Task Name	Duration	Start	Finish	January 2017	February 2017	March 2017	April 2017	May 2017	June 2017	July 2017	August 2017	September
77	Curb formwork install	0.5 days	Fri 6/30/17	Fri 6/30/17									
78	Backfill island to grade with road base	0.5 days	Fri 6/30/17	Fri 6/30/17									
79	8 - Electrical Trenching	9 days	Mon 7/3/17	Fri 7/14/17									
80	Set up flaggers, work perimeter, temp signs	0 days	Mon 7/3/17	Mon 7/3/17									
81	Excavate and trench west	2 days	Tue 7/4/17	Wed 7/5/17									
82	Tie in drainage	2 days	Thu 7/6/17	Fri 7/7/17									
83	Tie in electrical	1 day	Mon 7/10/17	Mon 7/10/17									
84	Backfill to grade with road base	1 day	Tue 7/11/17	Tue 7/11/17									
85	Excavate and trench east road	2 days	Thu 7/6/17	Fri 7/7/17									
86	Tie in electrical for east road	1 day	Mon 7/10/17	Mon 7/10/17									
87	Backfill to grade with road base	1 day	Wed 7/12/17	Wed 7/12/17									
88	Excavate for channelized island addition	0.5 days	Thu 7/13/17	Thu 7/13/17									
89	Curb formwork prep	0.5 days	Thu 7/13/17	Thu 7/13/17									
90	Curb formwork install	0.5 days	Fri 7/14/17	Fri 7/14/17									
91	Backfill island to grade with road base	0.5 days	Fri 7/14/17	Fri 7/14/17									
92	9 - Roundabout Construction	8 days	Fri 7/14/17	Tue 7/25/17									
93	Set up flaggers, work perimeter, temp signs	0 days	Fri 7/14/17	Fri 7/14/17									
94	Scrape top layer of roundabout	0.5 days	Mon 7/17/17	Mon 7/17/17									
95	Form Prep for roundabout, north channelized island, and temp	2 days	Mon 7/17/17	Tue 7/18/17									

Project Roundabout Construct
Date: Thu 3/2/17


Task Milestone Summary Critical

Page 5


ID	Task Name	Duration	Start	Finish
96	Form install on roundabout	1 day	Wed 7/19/17	Wed 7/19/17
97	Form install on channelized	1 day	Thu 7/20/17	Thu 7/20/17
98	Form install on temp bus accommodation	1 day	Fri 7/21/17	Fri 7/21/17
99	Pour remaining structures	1 day	Sat 7/22/17	Sat 7/22/17
100	Strip formwork	2 days	Mon 7/24/17	Tue 7/25/17
101	10 - Paving and Painting	11 days	Tue 7/25/17	Wed 8/9/17
102	Set up flaggers, work perimeter, temp signs	0 days	Tue 7/25/17	Tue 7/25/17
103	Paving milled road surface	5 days	Wed 7/26/17	Tue 8/1/17
104	Backfill with soil to grade and plant grass on new islands	5 days	Wed 8/2/17	Tue 8/8/17
105	Painting crosswalk, bike lanes, lane	3 days	Wed 8/2/17	Fri 8/4/17
106	Area cleanup	1 day	Wed 8/9/17	Wed 8/9/17
107	11 - Demobilization	2 days	Thu 8/10/17	Fri 8/11/17
108	2.0 - Project Close-out	10 days	Mon 8/14/17	Fri 8/25/17
109	Utilities commissioning	5 days	Mon 8/14/17	Fri 8/18/17
110	Prepare and submit O&M	10 days	Mon 8/14/17	Fri 8/25/17
111	END	0 days	Fri 8/25/17	Fri 8/25/17




Appendix J –Construction Schedule: Phase 2 - Gateway



Project: Gateway Construction
 Date: Fri 3/24/17





Project: Gateway Construction
Date: Fri 3/24/17

Task Milestone

Summary Critical

Appendix K –Traffic Management Plan Checklist

Table 3.1: Initial Project Category Assessment

Traffic Consideration	Value	✓	Point Value	Score
Posted or Statutory Speed Speed limit of the roadway.	≤ 50 km/hr.	✓	1 point	1
	60 - 70 km/hr.	<input type="checkbox"/>	3 points	
	≥ 80 km/hr.	<input type="checkbox"/>	4 points	
Traffic Volume Traffic volume (in both directions) in peak hours.	< 1,000 vehicles/hr.	<input type="checkbox"/>	1 point	3
	1,000 to 3,000 vehicles/hr.	✓	3 points	
	> 3,000 vehicles/hr.	<input type="checkbox"/>	4 points	
Lanes Number of lanes in both directions.	2 lanes.	✓	1 point	1
	3 lanes.	<input type="checkbox"/>	3 points	
	4 lanes or more.	<input type="checkbox"/>	4 points	
Encroachment Location of work.	Off roadway.	<input type="checkbox"/>	0 point	4
	Shoulder work/partial lane closure.	<input type="checkbox"/>	3 points	
	Full lane closure, ramp closure, or intersection closure.	✓	4 points	
Detours	No detour.	<input type="checkbox"/>	0 point	4
	Detour traffic on temporary roadway next to work zone.	<input type="checkbox"/>	3 points	
	Route takes traffic off regular route away from work zone; requires detour signing.	✓	4 points	
Duration of Work	Short-duration work (no more than one day-time shift).	<input type="checkbox"/>	1 point	4
	Long-duration work (less than 2 weeks).	<input type="checkbox"/>	2 points	
	Long-duration work (more than two weeks).	✓	4 points	
Allowable Delays Delay time plus time to travel through work zone in minutes.	< 20 minutes.	✓	1 point	1
	≥ 20 minutes.	<input type="checkbox"/>	3 points	
	No allowable delay.	<input type="checkbox"/>	4 points	

Traffic Consideration	Value	✓	Point Value	Score
Time of Day Time of day that work will occur.	Day-time only work (DT).	<input type="checkbox"/>	1 point	3
	Active day-time work, with traffic control devices in place at night (DTN).	<input checked="" type="checkbox"/>	3 points	
	Active night-time work (NT).	<input type="checkbox"/>	4 points	
Vertical Alignment	Flat terrain.	<input checked="" type="checkbox"/>	0 point	0
	Rolling terrain.	<input type="checkbox"/>	1 point	
	Mountainous terrain.	<input type="checkbox"/>	2 point	
Horizontal Alignment	Work zone and approaches on tangent.	<input checked="" type="checkbox"/>	0 point	0
	Curve in work zone; no reduced speed advisory for curve.	<input type="checkbox"/>	1 point	
	Curve in work zone with reduced speed advisory.	<input type="checkbox"/>	2 point	
Signalization	No signal in work zone.	<input checked="" type="checkbox"/>	0 point	0
	Signal in work zone with left- or right-turn arrows.	<input type="checkbox"/>	1 point	
	Signal in work zone with left- <u>and</u> right-turn arrows.	<input type="checkbox"/>	4 points	
Runaway Lanes	No runaway lanes in work zone.	<input checked="" type="checkbox"/>	0 point	0
	Runaway lanes within or near work zone; they will not be blocked at any time during course of work.	<input type="checkbox"/>	1 point	
	Runaway lanes within or near work zone; they may be blocked by work or queues during course of work.	<input type="checkbox"/>	4 points	
Pedestrians and Cyclists	No pedestrians or cyclists in work zone.	<input type="checkbox"/>	0 point	3
	Pedestrians and cyclists could be in/near work zone.	<input type="checkbox"/>	2 point	
	Designated cycle route or multi-use pathway in work zone.	<input checked="" type="checkbox"/>	3 points	

Traffic Consideration	Value	✓	Point Value	Score
Roundabout	No roundabout in work zone.	<input checked="" type="checkbox"/>	0 point	0
	Single lane roundabout in work zone.	<input type="checkbox"/>	2 point	
	Multilane roundabout in work zone.	<input type="checkbox"/>	4 points	
HOV or Bus Lane	No HOV or bus lane in work zone.	<input checked="" type="checkbox"/>	0 point	0
	HOV or bus lane in work zone.	<input type="checkbox"/>	4 points	
Counter-Flow Lane	No counter-flow lane within work zone.	<input checked="" type="checkbox"/>	0 point	0
	Counter-flow lane within work zone (CF).	<input type="checkbox"/>	4 points	
			Total Score	24
			Category 1	< 16
			Category 2	16 to 25
			Category 3	> 25
			Initial Project Category	2

3.3.2 Project Risk Analysis

A project risk analysis is the process of reviewing site-specific characteristics and considering the likelihood and consequence of each item listed. It is able to highlight potential hazards that are not captured in the Initial Project Category Assessment.

Each project has a unique combination of site-specific characteristics, and the risk analysis considers potential hazards associated with the specific project and/or location.

Table 3.2: Project Risk Analysis on the following pages is used to determine whether each potential hazard creates a low, medium, or high risk for the project and location.

The total point value calculated at the end of Table 3.2 indicates that the project is assessed as a low-risk, medium-risk, or high-risk project.

Combining the results of the initial project category assessment and the risk analysis will determine the final project category (see [Section 3.3.3: Final Project Category Determination](#)).

Table 3.2: Project Risk Analysis

Item	Risk	Definition	✓	Point Value	Score
Falling object	Low	Potential of falling object through course of work (i.e., overhead works, slung loads, or equipment boom/bucket work).	<input checked="" type="checkbox"/>	1 point	1
	Medium	Working within a known avalanche or rock fall area; no recent evidence of activity.	<input type="checkbox"/>	2 points	
	High	Recent evidence of rock or material entering work site or overhead work that may impact travelling public or worker safety (i.e., overhead structures). Vehicle queues may back into a rock fall or avalanche area.	<input type="checkbox"/>	3 points	
Nature of work activity	Low	Work activity is not expected to create a significant hazard.	<input type="checkbox"/>	1 point	2
	Medium	Work activity will create excessive dirt, dust, or gravel on the road surface, and will thereby create a potential hazard.	<input checked="" type="checkbox"/>	2 points	
	High	Work activity such as blasting, scaling, or excavation < 2 metres from active travelling lanes will create a potential hazard.	<input type="checkbox"/>	3 points	
Removal of safety devices	Low	No removal of safety devices.	<input type="checkbox"/>	1 point	2
	Medium	Removal of safety devices such as pavement markings, signage, traffic signal, or reflectors.	<input checked="" type="checkbox"/>	2 points	
	High	Removal of containment devices, such as barrier, guard rail, crash attenuators, fencing, etc.	<input type="checkbox"/>	3 points	
Equipment movement through work zone	Low	Minimal conflict with traffic (e.g., work commencing off travelled roadway).	<input type="checkbox"/>	1 point	2
	Medium	Conflict with normal traffic flow; no queuing or traffic stoppages.	<input checked="" type="checkbox"/>	2 points	
	High	Conflicts with normal traffic; may create queuing and require traffic stoppages. Difficult for equipment to enter and exit site.	<input type="checkbox"/>	3 points	

Item	Risk	Definition	✓	Point Value	Score
Roadway surface condition during construction	Low	Roadway surface is maintained.	<input type="checkbox"/>	1 point	2
	Medium	Roadway surface, such as milling and grinding (consistent surface), creates a hazard for road users.	<input checked="" type="checkbox"/>	2 points	
	High	Roadway surface is inconsistent, with multiple changes or work tasks (manholes, culvert installation, etc.).	<input type="checkbox"/>	3 points	
Storage of equipment and material	Low	Stored outside clear zone.	<input checked="" type="checkbox"/>	1 point	1
	Medium	Stored within clear zone but outside travelled roadway.	<input type="checkbox"/>	2 points	
	High	Stored on shoulder but encroaching on travelled roadway.	<input type="checkbox"/>	3 points	
Load restrictions as a result of construction	Low	No load restrictions.	<input checked="" type="checkbox"/>	1 point	1
	Medium	Narrow lanes restrict wide loads	<input type="checkbox"/>	2 points	
	High	Overweight/overheight vehicles restricted (may result in structural damage).	<input type="checkbox"/>	3 points	
Lane widths	Low	Maintain existing lane widths.	<input type="checkbox"/>	1 point	3
	Medium	n/a	-	n/a	
	High	Lane width not maintained throughout work zone, or Single-lane alternating traffic.	<input checked="" type="checkbox"/>	3 points	
Work zone or queues block access (active or inactive site)	Low	None.	<input checked="" type="checkbox"/>	1 point	1
	Medium	Side street or business access.	<input type="checkbox"/>	2 points	
	High	Major public facility and/or major secondary roadway.	<input type="checkbox"/>	3 points	
Transit access	Low	No transit or school bus stops.	<input type="checkbox"/>	1 point	3
	Medium	Community shuttle or school bus stops.	<input type="checkbox"/>	2 points	
	High	Express transit or major bus route.	<input checked="" type="checkbox"/>	3 points	
Impacts of special events	Low	No known event.	<input checked="" type="checkbox"/>	1 point	1
	Medium	Moderate public event with attendance under 5,000.	<input type="checkbox"/>	2 points	
	High	Major public event with attendance over 5,000 or moderate public event (under 5,000) with no alternative access or route.	<input type="checkbox"/>	3 points	

Item	Risk	Definition	✓	Point Value	Score
Overlapping work	Low	No overlapping work.	<input type="checkbox"/>	1 point	2
	Medium	Another work site within 3 km; traffic control for the projects could impact one another.	<input checked="" type="checkbox"/>	2 points	
	High	Work sites adjacent or overlapping.	<input type="checkbox"/>	3 points	
Emergency facility access	Low	No emergency facility near work site.	<input checked="" type="checkbox"/>	1 point	1
	Medium	24-hour manned emergency facility.	<input type="checkbox"/>	2 points	
	High	Volunteer-staffed emergency facility; consider responder access to facility and emergency response.	<input type="checkbox"/>	3 points	
Total Score					22
Low Risk					< 23
Medium Risk					23 to 28
High Risk					> 28
Project Risk					Low

Note: If significant project-specific hazards are not included in the risk analysis above, the Evaluator may consider increasing the final risk rating. This modification and the justification for it should be documented.

All high-risk, project-specific hazards should be addressed and mitigated in the Traffic Management Plan.

3.3.3 Final Project Category Determination

The matrix in [Table 3.3: Final Project Category Determination](#) should be used to make the final project category determination.

It combines the initial project category assessment with the results of the risk analysis to identify a final project category based on roadway and traffic characteristics and risks.

It may be appropriate to increase the final category level for high-risk projects to reflect the complexity or hazards associated with the work.

Table 3.3: Final Project Category Determination

		Initial Project Category Assessment		
		1	2	3
Project Risk	Low	Category 1	Category 2	Category 3
	Medium	Category 1	Category 2	Category 3
	High	Category 2	Category 3	Category 3

The final project category determination should be used to identify required and recommended sub-plans and special conditions addressed in the Traffic Management Plan. This process is a guide and may not capture all components of the project which should be considered when determining the Project Category.

Appendix L –Cost Estimate

Pre-Construction Consultation Costs			
Description	Rate	Hours	Cost
Preliminary Design:			\$95,600
Project Engineer (E3)	\$159	160	\$25,440
Traffic Specialist Engineer (E4)	\$195	160	\$31,200
Management Engineer (E5)	\$223	80	\$17,840
CAD Technician/Technologist (T3)	\$132	160	\$21,120
Surveying:			\$20,400
Lead Surveyor (T4)	\$144	80	\$11,520
Assistant Surveyor (T2)	\$111	80	\$8,880
Geotechnical Evaluation			\$34,960
Geotechnical Engineer (E4)	\$195	80	\$15,600
Engineer-in-Training (E1)	\$121	160	\$19,360
Detailed Design:			\$60,820
Project Engineer (E3)	\$159	80	\$12,720
Traffic Specialist Engineer (E4)	\$195	40	\$7,800
Management Engineer (E5)	\$223	20	\$4,460
CAD Technician/Technologist (T3)	\$132	80	\$10,560
Structural EIT (E1)	\$121	80	\$9,680
Structural Engineer (E4)	\$195	80	\$15,600
Contractor Selection and Preparation			\$42,950
Project Engineer (E3)	\$159	200	\$31,800
Management Engineer (E5)	\$223	50	\$11,150
Total:			\$254,730

Roundabout Construction		
Division	Description	Cost
1	General Requirements	\$ 366,334.94
2	Site Construction	\$ 270,521.31
3	Concrete	\$ 68,977.60
15	Electrical	\$ 60,000.00
16	Sum	\$ 765,833.85
	Fee @ 10%	\$ 76,583.38
	Contingency @ 5%	\$ 38,291.69
	Total	\$ 880,708.93

Gateway Construction		
Division	Description	Cost
1	General Requirements	\$ 186,555.35
2	Site Construction	\$ 10,790.00
3	Concrete	\$ 173,493.50
5	Metals	\$ 103,518.79
6	Wood and Plastics	\$ 46,398.03
7	Thermal and Moisture Pr	\$ 8,000.00
8	Doors and Windows	\$ 50,160.00
	Sum	\$ 578,915.67
	Fee @ 10%	\$ 57,891.57
	Contingency @ 5%	\$ 28,945.78
	Total	\$ 665,753.02

ROUNDABOUT ESTIMATE BREAKDOWN

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
Div 1 General Expenses (Indirects)									Division Total	\$ 366,334.94
Permitting										
Excavation allowance	1	\$ 2,000.00	LS							\$ 2,000.00
Electrical	1	\$ 1,985.00	EA							\$ 1,985.00
Tree removal	0	\$ 66.00	EA							\$ -
Signage permit	1	\$ 93.00	EA							\$ 93.00
Noise by/law	1	\$ 148.00	EA							\$ 148.00
UBC Parking Permit x 20	3	\$ 1,895.00	MO							\$ 5,685.00
Mobilization and Demobilization										
Phase 1										
Washroom mob	1	\$ 300.00	EA	SC						\$ 300.00
Trailer mob	1	\$ 300.00	EA	SC						\$ 300.00
Trash bin mob	1	\$ 300.00	EA	SC						\$ 300.00
Excavator mob	1	\$ 300.00	EA	SC						\$ 300.00
Fencing mob	1	\$ 300.00	EA	SC						\$ 300.00
Phase 4										
Fencing mob	1	\$ 300.00	EA	SC						\$ 300.00
Phase 6										
Fencing mob	1	\$ 300.00	EA	SC						\$ 300.00
Phase 9										
Fencing demob	1	\$ 300.00	EA	SC						\$ 300.00
Phase 11										
Washroom demob	1	\$ 300.00	EA	SC						\$ 300.00
Trailer demob	1	\$ 300.00	EA	SC						\$ 300.00
Trash bin demob	1	\$ 300.00	EA	SC						\$ 300.00
Excavator demob	1	\$ 300.00	EA	SC						\$ 300.00
Fencing demob	1	\$ 300.00	EA	SC						\$ 300.00

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
Div 2 Site Construction									Division Total	\$ 270,521.31
Site Preparation										
Pavement removal to subgrade										
Excavation	1130.3	\$ 32.29	M2	SC						\$ -
Trench box	1.0	\$ 60.00	M3	SC						\$ 67,818.51
		\$ 10,000.00	LS	SC						\$ 10,000.00
pavement milling 50mm deep										
Phase 6	611.0	\$ 7.85	M2	SC						\$ -
Phase 7	1517.0	\$ 7.85	M2	SC						\$ 4,794.95
		\$ 10,000.00	LS	SC						\$ 11,904.97
Truck and Transfer	1.0	\$ 10,000.00	LS	SC						\$ 10,000.00
Backfill										
Road Base 19mm Minus	1426.2	\$ 12.00	TON	SC						\$ 17,114.34
Density		1654	KG/M3							
Volume		862.3	M3							
Mass		1426.195209	TON							
Sub-base 75mm Minus	425.4	\$ 11.50	TON	SC						\$ 4,891.83
Density		1587	KG/M3							
Volume		268.0	M3							
Mass		425.3765071	TON							
Drain Rock 20mm Fractured	60.7	\$ 17.30	TON	SC						\$ 1,050.12
Density		1670	KG/M3							
Volume		36.3	M3							
Mass		60.700325	TON							
Soil Testing	1.0	\$ 10,000.00	LS	SC						\$ 10,000.00
Landscaping										
Grass	729	\$ 9.00	M2	SC						\$ 6,561.00
Soil	583.2	\$ 8.00	M3	SC						\$ 4,665.60
Soil Install by Subcontractor	5	\$ 312.00	DAYS	SC	Labourer	3	\$ 60.00	8	5	\$ 8,760.00
1CY Bucket Excavator x 1					Operator	1	\$ 75.00	8	5	\$ 3,000.00
					Foreman	1	\$ 85.00	8	5	\$ 3,400.00
Paving										
Paving	2128.0	\$ 20.00	M2	SC						\$ 42,560.00
Stormwater										
Allowance	1	\$ 60,000.00	LS	SC						\$ 60,000.00
Painting										
Allowance	1	\$ 4,000.00	LS	SC						\$ 4,000.00

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
Div 3 Concrete									Division Total	\$ 68,977.60
Curbs										
Formwork										
Phase 4	61	\$ -	LM	SC						\$ -
Phase 5	160	\$ -	LM	SC						\$ -
Phase 8	82	\$ -	LM	SC						\$ -
Phase 9	153	\$ -	LM	SC						\$ -
Curb Pour										
Phase 5	211	\$ 17.00	LM	SC						\$ 3,587.00
Phase 9	180	\$ 17.00	LM	SC						\$ 3,060.00
Strip	847	\$ -	LM	SC						\$ -
Roundabout										
Formwork										
Phase 9 - truck apron	33.67	\$ 32.29	M2	SP	Carpenters	3	60	8	3	\$ 5,407.16
Concrete										
Phase 9 - truck apron	62.5	\$ 600.00	M3	SC	Carpenters	2	60	4	1	\$ 37,980.00
Strip	0	\$ -	M2	SP	Carpenters	2	60	8	2	\$ 1,920.00
Sidewalk										
Formwork										
Phase 7	25.5	\$ 32.29	M2	SP	Carpenters	2	60	4	1	\$ 1,303.44
Curb Pour										
Phase 7	24.6	\$ 600.00	M3	SC	Carpenters	2	60	4	1	\$ 15,240.00
Strip	25.5	\$ -	M2	SP	Carpenters	2	60	4	1	\$ 480.00
Div 16 Electrical									Division Total	\$ 60,000.00
Electrical	1	\$ 60,000.00	LS	SC						\$ 60,000.00

GATEWAY ESTIMATE BREAKDOWN

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
Div 1 General Expenses (Indirects)									Division Total	\$ 186,555.35
Permitting										
Signage permit	1	\$ 93.00	EA							\$ 93.00
Noise bylaw	1	\$ 148.00	EA							\$ 148.00
UBC Parking Permit x 20	2	\$ 1,895.00	MO							\$ 3,790.00
Mobilization and Demobilization										
Washroom mob	1	\$ 300.00	EA	SC						\$ 300.00
Trailer mob	1	\$ 300.00	EA	SC						\$ 300.00
Trash bin mob	1	\$ 300.00	EA	SC						\$ 300.00
Excavator mob	1	\$ 300.00	EA	SC						\$ 300.00
Fencing mob	1	\$ 300.00	EA	SC						\$ 300.00
90 ton crane mob	1	\$ 500.00	EA	SC						\$ 500.00
Washroom demob	1	\$ 300.00	EA	SC						\$ 300.00
Trailer demob	1	\$ 300.00	EA	SC						\$ 300.00
Trash bin demob	1	\$ 300.00	EA	SC						\$ 300.00
Excavator demob	1	\$ 300.00	EA	SC						\$ 300.00
Fencing demob	1	\$ 300.00	EA	SC						\$ 300.00
90 ton crane mob	1	\$ 500.00	EA	SC						\$ 500.00
Rentals										
Fencing										
During gateway construction	130		LM							
32 days	1.0322581	\$ 7.00	/LM/MO							\$ 939.35
Washroom x 1	2	\$ 300.00	MO	SC						\$ 600.00
8 x 24 Trailer x 1	2	\$ 300.00	MO	SC						\$ 600.00
12YD Trash bin x 1	2	\$ 200.00	MO	SC						\$ 400.00
5kW Generator x 1	2	\$ 800.00	MO	SC						\$ 1,600.00
20kW Generator x 1	2	\$ 1,500.00	MO	SC						\$ 3,000.00
90 ton mobile hydraulic crane	268	\$ 150.00	HOUR	SC	Operator	1	\$ 80.00	8		\$ 61,640.00
Genie Boom Lift Z45' 4x4 (Manlift A)	5	\$ 1,200.00	WK	SC						\$ 6,000.00
Genie Boom Lift Z45' 4x4 (Manlift B)	5	\$ 1,200.00	WK	SC						\$ 6,000.00
Project Staff										
Project Manager	1	\$ -	EA	SP		1	\$ 120.00	2		\$ 8,040.00
Superintendent	1	\$ -	EA	SP		1	\$ 130.00	8		\$ 34,840.00
Surveyor	1	\$ -	EA	SP		1	\$ 60.00	4		\$ 8,040.00
Subcontractors										
Flaggers										
During gateway construction	3	\$ -	EA	SC		2	\$ 50.00	8		\$ 26,800.00
Flagging work truck x 1	33.5	\$ 150.00	DAYS	SC						\$ 5,025.00
Signage allowance	1	\$ 5,000.00	LS	SP						\$ 5,000.00

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
O&M Manual										
Allowance	1	\$ 10,000.00	LS							\$ 10,000.00
Div 2 Site Construction									Division Total	\$ 10,790.00
Grass protection										
GPM12 GROUND PROTECTION MATS install and remove	15	\$ 162.00	EA		Carpenters Foreman	2 1	60 90	8 8	2 2	\$ 2,430.00 \$ 1,920.00 \$ 1,440.00 \$ 5,000.00
Grass rehab allowance	1	\$ 5,000.00	LS							
Div 3 Concrete									Division Total	\$ 173,493.50
Walkway										
Formwork & Rebar										
Fdn fmwk & rebar	57.12	\$ 32.29	M2	SP	Carpenters Foreman	3 1	60 90	8 8	1.5 1.5	\$ 4,004.50 \$ 1,080.00
Walkway pour										
L	14		LM							
W	2		LM							
D	0.04		LM							
no. of walkways	1		EA							
Volume	1.12	\$ 600.00	M3		Carpenters Foreman	2 1	60 90	4 4	1 1	\$ 1,152.00 \$ 360.00
Strip										
57.12	\$ -		M2	SP	Carpenters Foreman	2 1	60 90	4 4	1 1	\$ 480.00 \$ 360.00
Precast Rebar										
Rebar to conc ratio	0.7692308									
Conc density	2400		KG/M3							
Fdn Conc weight	2688		KG							
Fdn Rebar weight	2067.6923		KG							
Fdn Rebar cost	4558.4812	\$ 0.80	LBS							\$ 3,646.78
Gateway Foundations										
1.1 Observation Deck										
Formwork & Rebar										
Fdn fmwk & rebar	32	\$ 32.29	M2	SP	Carpenters Foreman	3 1	60 90	8 8	1 1	\$ 2,473.34 \$ 720.00
Concrete Fdn SOG										
L	2		LM							
W	2		LM							
D	1		LM							
No. of fdns	4		EA							
Volume	16	\$ 600.00	M3	SC	Carpenters Foreman	2 1	60 90	6 6	1 1	\$ 10,320.00 \$ 540.00
Strip										
32	\$ -		M2	SP	Carpenters Foreman	2 1	60 90	4 4	1 1	\$ 480.00 \$ 360.00

Description	Quantity	Unit Cost	UoM	(Sub)Contract	Labour	Labour Qty	Labour Unit Cost	Hours/Day	Days	Subtotal
Div 5 Metals									Division Total	\$ 103,518.79
Gateway Structure										
Steel cost/lb		\$	2.76	SC						
1) Deck Girder (GL B, 3-4)										
W360x134	2		EA							
L	14		LM							
Load/m	1.31		KN/LM							
Load	36.68		KN							
steel weight	3742.8571	\$	2.76	SC						\$ 10,316.25
2) Deck Span Bracing (Lateral Stability and Torsional Stiffness)										
Brace length	2		LM							
Spacing @	3		LM							
Deck Span	14		LM							
W360x33	5		EA							
L	10		LM							
Load/m	0.321		KN/LM							
Load	16.05		KN							
steel weight	1637.7551	\$	2.76	SC						\$ 4,514.06
3) Steel Column (B3) Supporting Steel Deck										
HSS 89x89x6.4	2		EA							
L	6		LM							
Load/m	0.153		KN/LM							
Load	1.836		KN							
steel weight	187.34694	\$	2.76	SC						\$ 516.38
4) Steel Column (A1 A2 B1 B2) Supporting Landing										
HSS 89x89x6.4	4		EA							
L	3.5		LM							
Load/m	0.153		KN/LM							
Load	2.142		KN							
steel weight	218.57143	\$	2.76	SC						\$ 602.44
5) Staircase Landing Beam										
W360x33	2		EA							
L	2		LM							
Load/m	0.321		KN/LM							
Load	1.284		KN							
steel weight	131.02041	\$	2.76	SC						\$ 361.13
6) Observation Deck X-bracing										
L76x76x7.9	8		EA							
L	8.5		LM							
Load/m	0.0883		KN/LM							
Load	6.0044		KN							
steel weight	612.69388	\$	2.76	SC						\$ 1,688.74

Appendix M –Presentation Poster

REDESIGN OF CHANCELLOR BOULEVARD / WESBROOK MALL INTERSECTION

Nishchhal Gautam, Ryan Li, Jason Wen, Jeffrey Chun, Nathan Chan & Jessica Francis
The University of British Columbia – Civil Engineering




a place of mind
THE UNIVERSITY OF BRITISH COLUMBIA
Faculty of Applied Science

Project Background

UBC Campus and Community Planning has identified the Chancellor Boulevard and Wesbrook Mall intersection as the site for a redesign. The project objectives are:

- Accommodate safe travel for all modes of transportation
- Perform with minimal delays for future traffic volume
- Provide a “gateway” to the northern part of UBC Vancouver campus

The Project site can be seen below:



The existing intersection is a three way stop and yield control intersection that does not have pedestrian crossings. The existing layout can be seen below:



After completing traffic analysis for the existing intersection, a traffic light, and a roundabout it was determined to be the best solution based on the below criteria:

- Safety of pedestrians, cyclists, and vehicles
- Sustainability and aesthetics
- Intersection capacity
- Cost and construction schedule

Key Design Features

Intersection Safety

- Crosswalks and a boulevard for bicycles have been integrated
- Electrical connections for LED lighting at crosswalks
- Roundabouts facilitate slower speeds, minimizing chance of collision and reducing severity of collisions, collisions are also not head on
- There is a concrete apron within the roundabout that allows for heavy vehicles safely as well as maintenance for landscaping



Traffic Capacity

- Under current traffic volumes, the roundabout is expected to perform well with an average delay per vehicle of less than 5 seconds; the remaining scenarios operate with an average anticipated delay of approximately 10 seconds per vehicle
- Under 2040 projected traffic volumes, the roundabout performs significantly better than the alternatives



Economic Performance

- The increase in traffic capacity can reduce future costs and collateral effects such as increasing the traffic demand of other entrances.
- The construction of the roundabout is phased to allow for traffic flow in the area

Project Sustainability

- Overall there is a net gain of green space for the project site which improves storm water



Traffic Analysis

Intersection Configuration	Approach	Current AM	2040 AM
		Conditions	Conditions
Existing	East	5-10	40-60
	South	5-10	5-10
	West	5-10	5-10
Roundabout	East	<5	5-10
	South	<5	<5
	West	<5	5-10



Modelling

- 2040 AM Peak – Existing Intersection and Roundabout Design



Cost Estimate

DESIGN	TOTAL: \$254,750	
Preliminary Design	\$95,600	
Detailed Design	\$116,200	
Contract Administration and Construction Reviews	\$42,950	
CONSTRUCTION	TOTAL: \$976,360	
General Contractor	\$310,670	Gateway Structure \$119,770
Subcontracts	\$457,170	Fee \$88,760
ADDITIONAL BUDGETS		
Contingency	\$44,380	
Maintenance	\$15,300 per year	
	TOTAL: \$1,275,470	

Construction Schedule

